

4" PAVEMENT MARKING SCHEDULE

LOCATION	PREFORMED PLASTIC PAVEMENT MARKINGS, 4"		
	SKIP-DASH 30'-10'	EDGE LINE	DOUBLE CENTERLINE
	WHITE (FOOT)	YELLOW (FOOT)	YELLOW (FOOT)
BISSELL STREET			
STA. 102+29.89 LT TO STA. 104+35.55 LT	55		
STA. 102+31.68 LT TO STA. 104+84.02 LT		252	
STA. 102+33.97 RT TO STA. 104+83.97 RT		250	
STA. 102+35.94 RT TO STA. 104+83.28 RT	68		
STA. 104+83.97 TO STA. 110+70.42			1246
TOTAL	123	502	1246

LETTERS AND SYMBOLS SCHEDULE

LOCATION	PREFORMED PLASTIC PAVEMENT MARKINGS, LETTERS & SYMBOLS
	WHITE (SQ FT)
BISSELL STREET	
STA. 110+84.42 - 0.50' LT TO STA. 110+84.42 - 18.00' LT	18
TOTAL	18

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION	EARTH * EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	(CU YD)	(CU YD)	(CU YD)	(CU YD)
BISSELL STREET				
STA. 102+31.48 TO STA. 111+71.44	1350	1013	148	865 (+)
TOTAL	1350	1013	148	865 (+)

NOTES: * BASED ON 25% SHRINKAGE

PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	PRISMATIC CURB REFLECTOR	PAINT PAVEMENT MARKING		TEMPORARY PAVEMENT MARKING			LETTERS & SYMBOLS (SQ FT)
		ONE-WAY AMBER	CURB	RAISED MEDIAN	LINE 4"	LINE 6"	LINE 12"	
		(EACH)	YELLOW (FOOT)	YELLOW (SQ FT)	(FOOT)	(FOOT)	(FOOT)	
BISSELL STREET								
STA. 102+29.89 TO STA. 112+39.65		11						
	CURB		96					
	MEDIAN SURFACE			35				
	STOP BAR						143	
	CROSSWALK					559		
	SKIP-DASH 30'-10'				123			
	EDGE LINE				502			
	DOUBLE CENTERLINE				1246			
	YIELD BARS							18
TOTAL		11	96	35	1871	559	143	18

6" PAVEMENT MARKING SCHEDULE

LOCATION	PREFORMED PLASTIC PAVEMENT MARKINGS, 6" WHITE
	"CROSSWALK" (FOOT)
BISSELL STREET	
STA. 104+49.64 - 33.68' LT TO STA. 104+96.81 - 30.60' LT	47.3
STA. 104+55.07 - 39.34' LT TO STA. 104+91.27 - 36.97' LT	36.3
STA. 105+38.83 - 23.23' RT TO STA. 105+87.15 - 25.09' RT	48.4
STA. 105+49.76 - 29.66' RT TO STA. 105+82.23 - 30.91' RT	32.5
STA. 107+48.17 - 22.08' LT TO STA. 107+84.61 - 22.08' LT	36.4
STA. 107+52.06 - 28.08' LT TO STA. 107+79.35 - 28.08' LT	27.3
STA. 110+74.42 - 18.00' LT TO STA. 110+74.42 - 26.34' RT	44.3
STA. 110+80.42 - 18.00' LT TO STA. 110+80.42 - 28.23' RT	46.2
STA. 110+80.42 - 28.23' RT TO STA. 111+65.50 - 29.09' RT	84.6
STA. 110+82.76 - 34.27' RT TO STA. 111+58.39 - 35.11' RT	75.0
STA. 111+87.23 - 23.78' LT TO STA. 112+31.81 - 23.43' LT	44.7
STA. 111+92.35 - 29.72' LT TO STA. 112+28.47 - 29.46' LT	36.2
TOTAL	559

12" PAVEMENT MARKING SCHEDULE

LOCATION	PREFORMED PLASTIC PAVEMENT MARKINGS, 12" WHITE
	"STOP BAR" (FOOT)
BISSELL STREET	
STA. 104+57.47 - 43.19' LT TO STA. 104+74.12 - 44.61' LT	17
STA. 105+66.34 - 37.79' RT TO STA. 105+80.59 - 34.74' RT	15
STA. 107+52.86 - 32.08' LT TO STA. 107+65.02 - 33.60' LT	12
STA. 110+70.42 - 00.00' RT TO STA. 110+70.42 - 23.78' RT	24
STA. 111+15.64 - 38.86' RT TO STA. 111+54.61 - 39.12' RT	39
STA. 111+94.33 - 33.70' LT TO STA. 112+12.15 - 35.85' LT	18
STA. 112+39.65 - 00.00' LT TO STA. 112+39.65 - 17.55' LT	18
TOTAL	143

CONCRETE STEPS SCHEDULE

LOCATION	CONCRETE STEPS (CU YD)	PIPE HANDRAIL (FOOT)
BISSELL STREET		
STA. 103+01.24 - 42.90' LT TO STA. 103+04.77 - 43.46' LT	0.667	24.0
STA. 103+44.15 - 42.10' LT TO STA. 103+48.15 - 42.03' LT	0.791	28.0
STA. 103+60.27 - 40.83' LT TO STA. 103+64.27 - 40.77' LT	0.667	24.0
TOTAL	2.1	76

ORNAMENTAL METAL FENCE SCHEDULE

LOCATION	ORNAMENTAL METAL FENCE (FOOT)
BISSELL STREET	
STA. 110+53.78 - 33.35' LT TO STA. 111+69.38 - 29.79' LT	116
TOTAL	116