GENERAL NOTES

- NO UTILITY CONFLICTS ARE ANTICIPATED AS A PART OF THIS PROJECT, HOWEVER THE ENGINEER AND OWNER FURTHER DO NOT WARRANT THAT ALL UTILITIES HAVE BEEN ILLUSTRATED ON THESE DOCUMENTS. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR CONTACTING J.U.L.I.E. FOR FIELD VERIFICATION OF ALL UTILITIES ON THE SITE PRIOR TO COMMENCEMENT OF CONSTRUCTION. IF THE CONTRACTOR DETERMINES THAT SUBSTANTIAL DISCREPANCY EXISTS BETWEEN FIELD VERIFIED UTILITIES AND THESE PLANS WHICH WOULD SIGNIFICANTLY AFFECT THE FUNCTION, COST, OR PERFORMANCE OF THE PROJECT, THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE ENGINEER FOR CLARIFICATION AND PROJECT DIRECTION.
- ALL TRAFFIC CONTROL INCLUDING BUT NOT LIMITED TO, WORK ZONE, TEMPORARY, AND PERMANENT, SHALL BE FURNISHED, INSTALLED, MAINTAINED, RELOCATED, AND/OR REMOVED ACCORDING TO SECTION 700 OF THE LATEST EDITION OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.
- THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE VILLAGE OF GLEN CARBON AT LEAST FORTY-EIGHT (48) HOURS IN ADVANCE PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION ACTIVITIES OR WORK REQUIRING INSPECTION OR APPROVAL BY THE AFFECTED UNITS OF GOVERNMENT.

COMMITMENTS: NONE

SUMMARY OF QUANTITIES

Pay Item No.	Pay Item	Unit	Pay Item Total:
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	725
40600300	AGGREGATE (PRIME COAT)	TON	31
40600990	TEMPORARY RAMP	SQ YD	24
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,643
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	96
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQYD	28,701
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	19,043
48203100	HOT-MIX ASPHALT SHOULDERS	TON	738
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LSUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,040
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,040
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	\$Q FT	8,169
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19,838

*SPECIALTY ITEM

THOUVENOT. WADE & MOERCHEN, INC. ENGINEERS ♦ SLIRVEYORS ♦ PLANNERS

(TWM)

☐ CORPORATE OFFICE 4940 OLD COLLINSVILLE RD. SWANSEA, ILLINOIS 62226 TEL (618) 624-4488 FAX (618) 624-6688

☐ WATERLOO OFFICE 113 SOUTH MAIN STREET WATERLOO, ILLINOIS 62298 TEL (618) 939-5050 FAX (618) 939-3938

⊠ EDWARDSVILLE OFFICE 600 COUNTRY CLUB VIEW, SUITE EDWARDSVILLE, ILLINOIS 62025 TEL (618) 656-4040 FAX (618) 656-4343

ST. LOUIS OFFICE
720 CLIVE ST., SUITE 200AA
ST. LOUIS, MISSOURI 63101
TEL (314) 241-6300
FAX (314) 241-2391

ST. CHARLES OFFICE 400 N. 5TH STREET, SUITE 101 ST. CHARLES, MISSOURI 63301 TEL (636) 724-8300 FAX (636) 724-8304 UCENSE NO. 184-001220

81~006202

048-000029

HC 001528

PROFESSIONAL REGISTRATIONS BLINOS PROFESSIONAL DESIGN FRAI PROFESSIONAL ENGINEERING CORP. PROFESSIONAL STRUCTURAL ENGR. CORP. LINOS PROF, LAND SURVEYING CORP. MISSOURE PROFESSIONAL ENGR. CORP. MISSOURI LAND SURVEYING CORP.

SEAL

Signature Date:
Exploition Date:
Exploition Date:

STATEMENT OF RESPONSIBILITY
I hereby confirm that the document herein to be authenticated by my seed in restricted to this wheel, and I hereby disclaim any responsibility for all other drawings, specifications, selfandes, reports or other documents or hardwarfs residing to or leterated to be utilized for any other part of the architectural, engineering or survey project.

REV.	DATE	DESCRIPTION
Δ		
Δ		
Δ		· · · · · · · · · · · · · · · · · · ·

rawn Pi	OH SHEET
1.	2
HECKED f: M.	K OF 9 SHETS
	ж
OJECT T1908012	5C .
COLUCT DOD DEVIOUS	CL RESIDENCE CONTRACTOR

I ISSUED FOR CONSTR. II RECORD DRAWING