



- CORPORATE OFFICE**  
4940 OLD COLLINGSVILLE RD.  
SWANSEA, ILLINOIS 62226  
TEL (618) 624-4488  
FAX (618) 624-6888
- WATERLOO OFFICE**  
113 SOUTH MAIN STREET  
WATERLOO, ILLINOIS 62298  
TEL (618) 939-5050  
FAX (618) 939-3938
- EDWARDSVILLE OFFICE**  
600 COUNTRY CLUB VIEW, SUITE 1  
EDWARDSVILLE, ILLINOIS 62025  
TEL (618) 656-4040  
FAX (618) 656-4343
- ST. LOUIS OFFICE**  
720 OLIVE ST., SUITE 200AA  
ST. LOUIS, MISSOURI 63101  
TEL (314) 241-6300  
FAX (314) 241-2391
- ST. CHARLES OFFICE**  
400 N. 5TH STREET, SUITE 101  
ST. CHARLES, MISSOURI 63301  
TEL (636) 724-8300  
FAX (636) 724-8304

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ILLINOIS PROFESSIONAL DESIGN FIRM	184-001220
PROFESSIONAL ENGINEERING CORP.	62-035370
PROFESSIONAL STRUCTURAL ENGR. CORP.	81-000202
ILLINOIS PROF. LAND SURVEYING CORP.	948-000028
MISSOURI PROFESSIONAL ENGR. CORP.	MC 001528
MISSOURI LAND SURVEYING CORP.	MC 000366

SEAL

Signature: \_\_\_\_\_  
 Signature Date: \_\_\_\_\_  
 Expiration Date: \_\_\_\_\_

**STATEMENT OF RESPONSIBILITY**  
 I hereby confirm that the document herein to be authorized by my seal is restricted to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, schedules, reports or other documents or instruments relating to or intended to be utilized for any other part of the architectural, engineering or survey project.

PAVEMENT MARKINGS							
STATION	TO	STATION	DESCRIPTION	THERMOPLASTIC PAVEMENT MARKING - LINE 4" (DOUBLE SOLID YELLOW)	THERMOPLASTIC PAVEMENT MARKING - LINE 4" (SOLID YELLOW)	THERMOPLASTIC PAVEMENT MARKING - LINE 4" (SKIP-DASH 10'-30')	THERMOPLASTIC PAVEMENT MARKING - LINE 4" (SOLID WHITE)
				FEET	FEET	FEET	FEET
102+16.68	TO	104+51.14	CENTERLINE	468.92			
104+51.14	LT	TO 110+63.25	CENTERLINE SB		612.11		
104+51.14	RT	TO 110+63.25	CENTERLINE NB			150.00	
110+63.25	TO	132+62.30	CENTERLINE			550.00	
132+62.30	RT	TO 143+04.84	CENTERLINE NB		1042.54		
132+62.30	LT	TO 143+04.84	CENTERLINE SB			260.00	
143+04.84	TO	144+34.29	CENTERLINE	258.90			
144+34.29	RT	TO 154+15.54	CENTERLINE NB			250.00	
144+34.29	LT	TO 154+15.54	CENTERLINE SB		981.25		
154+15.54	TO	176+71.97	CENTERLINE			570.00	
176+71.97	RT	TO 180+06.69	CENTERLINE NB		334.72		
176+71.97	LT	TO 180+06.69	CENTERLINE SB			80.00	
102+16.68	RT	TO 111+28.25	NB EDGE LINE				911.57
102+16.68	LT	TO 111+13.91	SB EDGE LINE				897.23
111+72.51	LT	TO 114+59.55	SB EDGE LINE				287.04
112+05.25	RT	TO 117+52.05	NB EDGE LINE				546.80
115+17.18	LT	TO 124+00.78	SB EDGE LINE				883.60
118+03.25	RT	TO 121+31.15	NB EDGE LINE				327.90
121+87.65	RT	TO 124+29.05	NB EDGE LINE				241.40
124+61.25	LT	TO 126+25.25	SB EDGE LINE				174.00
124+99.05	RT	TO 127+63.85	NB EDGE LINE				264.80
126+79.25	LT	TO 134+88.44	SB EDGE LINE				809.19
128+08.85	RT	TO 129+63.15	NB EDGE LINE				154.30
130+08.55	RT	TO 131+99.85	NB EDGE LINE				191.30
132+40.69	RT	TO 152+97.72	NB EDGE LINE				2057.03
135+33.44	LT	TO 140+48.49	SB EDGE LINE				515.05
141+12.34	LT	TO 145+31.02	SB EDGE LINE				418.68
145+75.47	LT	TO 155+50.61	SB EDGE LINE				975.14
153+39.74	RT	TO 155+48.57	NB EDGE LINE				208.83
156+10.82	LT	TO 169+77.86	SB EDGE LINE				1367.04
156+28.52	RT	TO 166+45.99	NB EDGE LINE				1017.47
167+13.85	RT	TO 169+75.90	NB EDGE LINE				262.05
170+04.54	LT	TO 171+59.24	SB EDGE LINE				154.70
170+40.54	RT	TO 173+84.41	NB EDGE LINE				353.87
171+86.33	LT	TO 175+00.54	SB EDGE LINE				314.21
174+70.61	RT	TO 178+31.30	NB EDGE LINE				360.69
175+43.84	LT	TO 180+06.69	SB EDGE LINE				462.85
178+83.86	RT	TO 180+06.69	NB EDGE LINE				122.83
SUB-TOTAL:				727.82	2970.62	1860.00	14279.57
TOTAL:						19838.01	

PAVING SCHEDULE								
LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL, 1.5"	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N70	HOT-MIX ASPHALT SHOULDERS	AREA REFLECTIVE CRACK CONTROL TREATMENT	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE (PRIME COAT)	BIT. MATERIALS (PRIME COAT)	TEMPORARY RAMP
	SQ YD	TON	TON	SQ YD	TON	TON	GALLON	SQ YD
STA 102+16.68 TO 180+06.69	19,042.25	1,642.39		19,042.25		29		24
SHLDR RT 102+16.68 TO 104+02.40	77.38		6.67				5.80	
SHLDR RT 104+02.40 TO 155+48.57	2,858.98		246.59				214.42	
SHLDR RT 156+28.52 TO 180+06.69	1,321.21		113.95				99.09	
SHLDR LT 102+16.68 TO 105+03.97	119.70		10.32				8.98	
SHLDR LT 105+03.97 TO 180+06.69	4,168.18		359.51				312.61	
E. INGLE DRIVE	262.66				22.65	0.39		19.70
W. INGLE DRIVE	78.50				6.77	0.12		5.89
AUTUMN GLEN DRIVE	96.70				8.34	0.15		7.25
OAKDALE LAKE DRIVE	123.22				10.63	0.18		9.24
ASH ROAD	47.10				4.06	0.07		3.53
LAKEWOOD DRIVE	88.88				7.67	0.13		6.67
MARK TRAIL DRIVE	145.22				12.53	0.22		10.89
LUCINDA DRIVE	148.22				12.78	0.22		11.12
GRAINY DRIVE	122.33				10.55	0.18		9.17
TOTAL	28,700.63	1,642.39	737.04	19,042.25	95.98	30.23	724.37	24

**SCHEDULE OF QUANTITIES**

**GLEN CARBON ROAD  
RESURFACING PHASE III  
VILLAGE OF GLEN CARBON  
MADISON COUNTY, IL**

REV.	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY: PDH  
 DESIGNED BY: PDH  
 CHECKED BY: MJK  
 APPROVED BY: MJK

SHEET **3** OF 9 SHEETS

PROJECT NUMBER T19080125C

ISSUED FOR PREVIEW     ISSUED FOR BIDDING  
 ISSUED FOR CONSTR.     RECORD DRAWING