

FIELD ENTRANCE QUANTITIES		
ENTRANCES	AGGREGATE SURFACE COURSE TYPE B, TON	HOT MIX ASPHALT SURFACE COURSE, MIX "C", N70, TON
ONE (1) ENTRANCE	4	1
TOTAL = 19 ENTRANCES	76	19
MAILBOX TURNOUT QUANTITIES		
TURNOUT	BITUMINOUS MATERIALS (PRIME COAT) GALLON	HOT MIX ASPHALT SURFACE COURSE, MIX "C", N70, TON
ONE (1) TURNOUT	4	1
TOTAL = 31 TURNOUTS	32	8
PRIVATE ENTRANCE QUANTITIES		
ENTRANCES	BITUMINOUS MATERIALS (PRIME COAT) GALLON	HOT MIX ASPHALT SURFACE COURSE, MIX "C", N70, TON
ONE (1) ENTRANCE	10	3
TOTAL = 40 ENTRANCES	400	120
COMMERCIAL ENTRANCE QUANTITIES		
ENTRANCES	BITUMINOUS MATERIALS (PRIME COAT) GALLON	HOT MIX ASPHALT SURFACE COURSE, MIX "C", N70, TON
ONE (1) ENTRANCE	12	3
TOTAL = 3 ENTRANCES	36	9

SCHEDULE OF PAVEMENT MARKING LINE, 4"							
WESTBOUND LANE				EASTBOUND LANE			
STATION	NO PASSING (YELLOW SOLID)	CENTERLINE (YELLOW DASHED)	STATION	NO PASSING (YELLOW SOLID)	CENTERLINE (YELLOW DASHED)	STATION	EDGE LINE (WHITE SOLID)
198+14 TO 199+64	150		198+14 TO 207+94	980		198+14 TO 444+79	48745
199+64 TO 222+89		581	222+89 TO 231+19		208		
222+89 TO 226+39	350		231+19 TO 236+44	525			
231+19 TO 238+39		180	238+39 TO 247+19		220		
238+39 TO 247+64	925		247+19 TO 252+69	550			
247+64 TO 266+64		475	266+64 TO 274+69		201		
266+64 TO 271+39	475		274+69 TO 281+19	650			
274+69 TO 283+64		224	283+64 TO 292+19		214		
283+64 TO 286+74	310		292+19 TO 296+69	450			
292+19 TO 295+04		71	296+69 TO 303+69		175		
295+04 TO 302+64	760		303+69 TO 311+69	800			
303+69 TO 316+29		315	316+29 TO 324+94		216		
316+29 TO 319+39	310		324+94 TO 328+69	375			
324+94 TO 334+64		243	334+64 TO 343+44		220		
334+64 TO 341+14	650		343+44 TO 350+44	700			
343+44 TO 346+14		68	350+44 TO 354+94		113		
346+14 TO 351+64	550		354+94 TO 360+64	570			
354+94 TO 360+64		143	360+64 TO 369+69		226		
360+64 TO 367+64	700		369+69 TO 377+19	750			
369+69 TO 375+74		151	377+19 TO 384+44		181		
375+74 TO 380+89	515		384+44 TO 391+19	675			
384+44 TO 418+64		855	418+64 TO 425+64		175		
418+64 TO 425+64	700		425+64 TO 435+44	980			
425+64 TO 431+14		138	435+44 TO 438+69		81		
431+14 TO 444+79	1365		438+69 TO 443+19	450			
			443+19 TO 444+79		40		
TOTALS	7760	3444		8455	2270		48745

MILLING SCHEDULE	
LOCATION	COLD MILLING
STA. 198+14 TO 198+54	216
STA. 398+21 TO 400+71	611
STA. 131+77 TO 132+17	428
TOTAL	1255

SIDEROAD ENTRANCE QUANTITIES	
LOCATION	HOT MIX ASPHALT SURFACE COURSE, MIX "C", N70, TON
STA 211+34 RT	11.8
STA 211+40 LT	6.2
STA 238+37 LT	15
STA 238+37 RT	8.4
STA 319+32 LT	9.3
STA 319+32 RT	8.9
STA 346+16 RT	7.8
STA 372+92 LT	10
STA 372+92 RT	17.5
TOTAL = 9 SIDEROADS	92.90

MISCELLANEOUS DETAILS