

MODEL: SQO [Sheet]
FILE NAME: c:\pw_work\pwdo\illinois\gov\baraa.alsmadi\illinois\gov\10511551155101324-sh-SQO.dgn

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					ROADWAY	ROADWAY	SIGNALS			
					80% FED 20% STATE	100% STATE	80% FED 20% STATE			
	Code No.	Item	Unit	Total Quantity	0005	0005	0021			
	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	10842	10842					
	40600370	LONGITUDINAL JOINT SEALANT	FOOT	11822	11822					
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	37	37					
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	87	87					
	40605026	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 9.5, MIX "F", N80	TON	2362	2362					
	44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	24093	24093					
	44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	964	964					
	44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	723	723					
	44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	603	603					
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	106	106					
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2					
	63200310	GUARDRAIL REMOVAL	FOOT	50	50					
	64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	6620	6620					
	67100100	MOBILIZATION	L SUM	1	1					
	70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
	70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1					
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
	70102634	TRAFFIC CONTROL AND PROTECTION, STANDARD 701611	L SUM	1	1					
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	14378	14378					
	70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	4793	4793					
	70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SQ FT	116	116					

SUMMARY OF QUANTITIES					TYPE CODE					
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					ROADWAY	ROADWAY	SIGNALS			
					80% FED 20% STATE	100% STATE	80% FED 20% STATE			
	Code No.	Item	Unit	Total Quantity	0005	0005	0021			
	70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	FOOT	17661	17661					
	70300241	TEMPORARY PAVEMENT MARKING - LINE 6"- PAINT	FOOT	570	570					
	70300251	TEMPORARY PAVEMENT MARKING - LINE 8"- PAINT	FOOT	128	128					
	70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	FOOT	484	484					
	70300281	TEMPORARY PAVEMENT MARKING - LINE 24"- PAINT	FOOT	113	113					
	72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	113	113					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17667	17667					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	570	570					
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	128	128					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	484	484					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	113	113					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	378	378					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	378	378					
	78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	6599	6599					
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1			
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	765			765			
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	2			2			
*	88600100	DETECTOR LOOP, TYPE I	FOOT	272			272			
*	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	280			280			
	X2020110	GRADING AND SHAPING SHOULDERS	UNIT	67	67					

 REVISED SHEET 4/11/2025

	USER NAME = Baraa.Alsmadi	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL 53 - N OF UNIVERSITY PKWY TO RENWICK RD			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					112	FAP 0112 23 Smart	WILL	23	3
		CHECKED -	REVISED -					CONTRACT NO. 62V35				
	PLOT DATE = 1/29/2025	DATE -	REVISED -					ILLINOIS FED. AID PROJECT				
					SCALE:	SHEET 1	OF 2	SHEETS	STA.	TO STA.		