| | SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | CODE NO. | ITEM | UNIT | | 0005 80% FED 20% STATE ROADWAY | 0005 100% STATE | | | | |
| | 40600290 | BITUMINOUS MATERIALS (TACK COAT) | POUND | 6770 | 6770 | | | | | |
| | 40600370 | LONGITUDINAL JOINT SEALANT | FOOT | 2646 | 2646 | | | | | |
| | 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 16 | 16 | | | | | |
| | 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 76 | 76 | | | | | |
| | 40603200 | POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 4.75, N50 | TON | 414 | 414 | | | | | |
| | 40604172 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "E", N70 | TON | 983 | 983 | | | | | |
| | 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SQ YD | 10030 | 10030 | | | | | |
| | 44201785 | CLASS D PATCHES, TYPE I, 12 INCH | SQ YD | 25 | 25 | | | | | |
| | 44201789 | CLASS D PATCHES, TYPE II, 12 INCH | SQ YD | 100 | 100 | | | | | |
| | 44201794 | CLASS D PATCHES, TYPE III, 12 INCH | SQ YD | 50 | 50 | | | | | |
| | 44201796 | CLASS D PATCHES, TYPE IV, 12 INCH | SQ YD | 25 | 25 | | | | | |
| | 60920015 | PIPE CULVERTS TO BE CLEANED 15" | FOOT | 300 | | 300 | | | | |
| | 64200108 | SHOULDER RUMBLE STRIPS, 8 INCH | FOOT | 5224 | 5224 | | | | | |
| | ~~64200116~~ | ~~SHOULDER RUMBLE STRIPS, 16 INCH~~ | ~~FOOT~~ | ~~5224~~ | ~~5224~~ | | | | | |
| | 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | |
| | 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | 1 | | | | | |
| | 70100460 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 | L SUM | 1 | 1 | | | | | |
| | 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 6427 | 6427 | | | | | |
| | 70300150 | SHORT TERM PAVEMENT MARKING REMOVAL | SQ FT | 2143 | 2143 | | | | | |
| | 70300221 | TEMPORARY PAVEMENT MARKING - LINE 4" - PAINT | FOOT | 21537 | 21537 | | | | | |
| | 70300281 | TEMPORARY PAVEMENT MARKING - LINE 24" - PAINT | FOOT | 39 | 39 | | | | | |
| * | 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 5302 | 5302 | | | | | |
| * | 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 13 | 13 | | | | | |
| * | 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 43 | 43 | | | | | |

1

| | SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | CODE NO. | ITEM | UNIT | | 0005 80% FED 20% STATE ROADWAY | 0005 100% STATE | | | | |
| | 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 43 | 43 | | | | | |
| | 78300202 | PAVEMENT MARKING REMOVAL - WATER BLASTING | SQ FT | 2419 | 2419 | | | | | |
| | X6420114 | CENTER LINE - RUMBLE STRIP - 16" | FOOT | 2578 | 2578 | | | | | |
| | X6700407 | ENGINEER'S FIELD OFFICE, TYPE A (D1) | CAL MO | 6 | 6 | | | | | |
| * | X7800815 | HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH | FOOT | 1877 | 1877 | | | | | |
| | ~~Z0013798~~ | ~~CONSTRUCTION LAYOUT~~ | ~~L SUM~~ | ~~1~~ | ~~1~~ | | | | | |
| | Z0030850 | TEMPORARY INFORMATION SIGNING | SQ FT | 77.1 | 77.1 | | | | | |

1

* = SPECIALTY ITEMS

1 REVISED SHEET 4/14/2025

MODEL: SOQ01 [Sheet]
FILE NAME: c:\pw_work\pwidot\nicholas.babul\d0927952\D103124-sht-SOQ.dgn

| | | | |
|---|---|---|---|
| USER NAME = nicholas.babul | DESIGNED - | REVISED - | |
| | DRAWN - | REVISED - | |
| PLOT SCALE = | CHECKED - | REVISED - | |
| PLOT DATE = 12/9/2024 | DATE - | REVISED - | |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**
**US 20 (GRANT HWY.) [0.2 MI S/E OF HARMONY RD. TO GETTY RD.]**

SCALE: | SHEET 1 OF 1 SHEETS | STA. | TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 525 | FAP 0525 23 SMART | MCHENRY | 15 | 3 |
| | | CONTRACT NO. 62V53 | | |
| | ILLINOIS | FED. AID PROJECT | | |