

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FEDERAL 20% STATE	100% STATE				
				0005	0005				
20200100	EARTH EXCAVATION	CU YD	40	40					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	189	189					
25200110	SODDING, SALT TOLERANT	SQ YD	189	189					
25200200	SUPPLEMENTAL WATERING	UNIT	5	5					
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	11	11					
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	18835	18835					
40600370	LONGITUDINAL JOINT SEALANT	FOOT	23198	23198					
40600400	MIXTURE FOR CRACKS, JOINTS, AND	TON	63	63					
	FLANGEWAYS								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT	SQ YD	377	377					
	JOINT								
42001300	PROTECTIVE COAT	SQ YD	349	349					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5	SQ FT	2173	2173					
	INCH								
42400800	DETECTABLE WARNINGS	SQ FT	279	279					

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FEDERAL 20% STATE	100% STATE				
				0005	0005				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	41854	41854					
44000600	SIDEWALK REMOVAL	SQ FT	1783	1783					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	357	357					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	349	349					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	40	40					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	87	87					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	4	4					
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3	3					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	11	11					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	3	3					
60603800	COMBINATION CONCRETE CURB AND GUTTER,	FOOT	91	91					
	TYPE B-6.12								
60605000	COMBINATION CONCRETE CURB AND GUTTER,	FOOT	96	96					
	TYPE B-6.24								

USER NAME = Phillip Steed		DESIGNED -		REVISED -	
PLOT SCALE = \$SCALE\$		DRAWN -		REVISED -	
PLOT DATE = 2/4/2025		CHECKED -		REVISED -	
		DATE -		REVISED -	

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES FAP 370 (WESTERN AVE.)-S. OF BROADWAY ST. TO I-57				F.A.P. RTE. 370	
---	--	--	--	--	--	--	--	--------------------	--

MODEL: Default
FILE NAME: p:\1\lbt-pw-bentley.com\FWIDOT\Documents\DOT 0 cas\Dist\ct_1\ORBD Projects\106524\CADD\Drawings\CD\Drawings\csh-500.dgn

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FEDERAL 20% STATE	100% STATE					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80% FEDERAL 20% STATE	100% STATE						
				0005	0005									0005	0005						
78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	545	545						Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1							
	REMOVAL																				
										40604062	HOT-MIX ASPHALT SURFACE COURSE IL-9.5, MIX "D", N70	TON	3516	3516							
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	802	802																	
★K1004595	PRUNING FOR SAFETY AND EQUIPMENT	L SUM	1	1						70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	802	802							
	CLEARANCE																				
										70307210	TEMPORARY PAVEMENT MARKING - LINE 24" - TYPE IV TAPE	FOOT	2405	2405							
X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1																	
★X2010516	SELECTIVE CLEARING	UNIT	2	2																	
X4400501	COMBINATION CURB AND GUTTER REMOVAL AND	FOOT	230	230																	
	REPLACEMENT LESS THAN OR EQUAL TO 10																				
	FEET																				
X4400503	COMBINATION CURB AND GUTTER REMOVAL AND	FOOT	80	80																	
	REPLACEMENT GREATER THAN 10 FEET																				
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	1440		1440																
X6030310	FRAMES AND LIDS TO BE ADJUSTED	EACH	39	39																	
	(SPECIAL)																				
X6700407	ENGINEER'S FIELD OFFICE, TYPE A (D1)	CAL MO	12	12																	
X8860105	DETECTOR LOOP REPLACEMENT	FOOT	132	132																	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	70		70																
X7200061	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8																	
		USER NAME = Phillip.Steed	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION					SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	★ SPECIALTY ITEMS ☐ NON PARTICIPATING ITEMS		
			DRAWN -	REVISED -						FAP 370 (WESTERN AVE.)-S. OF BROADWAY ST. TO I-57				370	FAP 0370 23 SMART 2	COOK	33	5			
		PLOT SCALE = \$SCALE\$	CHECKED -	REVISED -						SCALE: NONE				SHEET OF SHEETS STA. TO STA.				ILLINOIS FED. AID PROJECT			
		PLOT DATE = 2/4/2025	DATE -	REVISED -														CONTRACT NO. 62V87			