



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 9, 2025

SUBJECT FAI ROUTE 57 (I-57)
SECTION (068-2323.3-CF) BR, I 24
COOK COUNTY
CONTRACT NO. 62X40
Item No. 50, April 25, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions
2. Revised pages 19, & 86 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF IMPROVEMENT	1
DESCRIPTION OF IMPROVEMENT	1
STRUCTURAL REPAIR OF CONCRETE	3
TEMPORARY SHORING AND CRIBBING.....	12
TRAFFIC CONTROL PLAN (D1)	12
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	13
KEEPING THE EXPRESSWAY OPEN TO TRAFFIC	17
TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	19
SPEED DISPLAY TRAILER (D1)	20
RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL.....	22
RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REPLACEMENT	22
GENERAL ELECTRICAL REQUIREMENTS (D1)	22
PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LUMINAIRES	40
STATUS OF UTILITIES (D-1).....	42
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES; CONCRETE, AND MORTAR (BDE)	45
COMPENSABLE DELAY COSTS (BDE).....	55
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	58
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE).....	60
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)...	62
PAVEMENT MARKING INSPECTION (BDE)	63
RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE).....	63
UNION PACIFIC RIGHT OF ENTRY	64
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	76
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	77
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	80
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	80
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	81
SUBMISSION OF PAYROLL RECORDS (BDE).....	81
SURVEYING SERVICES (BDE)	82
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	82
WEEKLY DBE TRUCKING REPORTS (BDE)	83
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....	83
WORKING DAYS (BDE)	85

Revised 4/9/2025

Private vehicles shall not be parked in the work zone. Contractor's equipment and/or vehicles shall not be parked on the shoulders or in the median during non-working hours. The parking of equipment and/or vehicles on state right-of-way will only be permitted at the locations approved by the Engineer.

Check barricades shall be placed every 1000' within a lane closure to prevent vehicles from driving through closed lanes.

Temporary ramp closures for service interchanges will only be permitted at night during the restricted hours listed for temporary one-lane closures within the project limits. However, no two adjacent entrance and exit ramps in one direction of the expressway shall be closed at the same time.

Freeway to freeway (system interchange) full ramp closures for two lane ramps will not be permitted. Partial ramp closures of system ramps may be allowed during the one-lane closure hours above. System ramp full closures for single lane ramps are only permitted for a maximum of four hours

- between the hours of 1:00 a.m. and 5:00 a.m. on Monday thru Friday
- between the hours of 1:00 a.m. and 6:00 a.m. on Saturday, and
- between the hours of 1:00 a.m. and 7:00 a.m. on Sunday.

The Contractor shall furnish and install large (48" X 48") "DETOUR with arrow" signs as directed by the Engineer for all system ramp closures. In addition, one portable changeable message sign will be required to be placed in advance of the ramp closure. The cost of these signs and PCMS board shall be included in the cost of traffic control and protection (six static signs maximum per closure).

Should the Contractor fail to completely open, and keep open, the ramps to traffic in accordance with the above limitations, the Contractor shall be liable to the Department for liquidated damages as noted under the Special Provision, "Failure to Open Traffic Lanes to Traffic".

TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS

Effective: October 25, 1995

Revised: January 21, 2015

The Contractor shall provide a person with a vehicle to survey, inspect and maintain all temporary traffic control devices when a lane is closed to traffic, when hazards are present adjacent to or within 10 foot of the edge of pavement for more than 24 hours, or as directed by the Engineer.

The surveillance person is required to drive through the project, to inspect all temporary traffic control devices, to correct all traffic control deficiencies, if possible, or immediately contact someone else to make corrections and to assist with directing traffic until such corrections are made, at intervals not to exceed four hours. This person shall list every inspection on an inspection form, furnished by the Engineer, and shall return a completed form on the first working day after the inspections are made.

The Contractor shall supply a telephone staffed on a 24-hour-a-day basis to receive any notification of any deficiencies regarding traffic control and protection or receive any request for improving, correcting or modifying traffic control, installations or devices, including pavement markings. The Contractor shall dispatch additional men, materials and equipment as necessary to begin to correct, improve or modify the traffic control as directed, within one hour of notification by this surveillance person or by the Department. Upon completion of such corrections and/or revisions, the Contractor shall notify the Department's communication center at (847) 705-4612.

Revised 4/9/2025

test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings. The barrier shall be capable of being moved on and off the roadway on a daily basis."

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within **50** working days.

FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC

Effective: March 22, 1996

Revised: February 9, 2005

Should the Contractor fail to completely open and keep open all the traffic lanes to traffic in accordance with the limitations specified under the Special Provisions for "Keeping the Expressway Open to Traffic", the Contractor shall be liable to the Department for the amount of:

One lane or ramp blocked = \$ **2,000**

Two lanes blocked = \$ **4,200**

Not as a penalty but as liquidated and ascertained damages for each and every 15 minute interval or a portion thereof that a lane is blocked outside the allowable time limitations. Such damages may be deducted by the Department from any monies due the Contractor. These damages shall apply during the contract time and during any extensions of the contract time.

Revised 4/9/2025