



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 16, 2025

SUBJECT FAI Route 70 (I-70)
Project NHPP-T230(819)
Section 82-1-B-1BJR-2
St. Clair County
Contract No. 76U30

Item No. 133, April 25th, 2025 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised pages i-ii of the Table of Contents of the Special Provisions.
3. Revised page 6 of the Special Provisions.
4. Revised sheets 2 and 4-5 of the plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
SUBMITTAL OF EEO/LABOR DOCUMENTATION	1
COMPLETION DATE (VIA CALENDAR DAYS) PLUS WORKING DAYS (BDE)	3
HOT-MIX ASPHALT SURFACE REMOVAL W/SKETCH OF ILLINOIS STANDARD W8-I107	4
TRAFFIC CONTROL PLAN	6
TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	6
DETOUR SIGNING	6
STATUS OF UTILITIES TO BE ADJUSTED	7
MODULAR EXPANSION JOINT	8
DECK SLAB REPAIR	12
BAR SPLICERS, HEADED REINFORCEMENT	17
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	19
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES; CONCRETE, AND MORTAR (BDE)	20
COMPENSABLE DELAY COSTS (BDE)	30
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	33
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	35
FULL LANE SEALANT WATERPROOFING SYSTEM (BDE)	38
HOT-MIX ASPHALT (BDE)	40
PAVEMENT MARKING INSPECTION (BDE)	41
PERFORMANCE GRADED ASPHALT BINDER (BDE)	41
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	46
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE)	47
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	50
SPEED DISPLAY TRAILER (BDE)	51
STEEL COST ADJUSTMENT (BDE)	52
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	54
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	55
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	55
SUBMISSION OF PAYROLL RECORDS (BDE)	56
SURVEYING SERVICES (BDE)	57
TRAINING SPECIAL PROVISIONS (BDE)	57
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION	59
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	61
WATERPROOFING MEMBRANE SYSTEM (BDE)	62

WEEKLY DBE TRUCKING REPORTS (BDE)..... 62
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 62

TRAFFIC CONTROL PLAN

Effective: July 12, 1993

Revised: May 12, 1997

Traffic control shall be in accordance with the applicable sections of the "Standard Specifications for Road and Bridge Construction", the applicable guidelines contained in the "National Manual on Uniform Traffic Control Devices for Streets and Highways", Illinois Supplement to the National Manual of Uniform Traffic Control Devices, these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to Articles 107.09 and 107.14 of the "Standard Specifications for Road and Bridge Construction" and the following Highway Standards relating to traffic control:

701101	701106	701400	701401	701402	701406
701426	701428	701446	701451	701456	701901

In addition, the following Special Provision(s) will also govern traffic control for this project:

Traffic Control and Protection, Standard 701451 (Special)
Detour Signing
Speed Display Trailer
Short Term and Temporary Pavement Markings
Vehicle and Equipment Warning Lights
Work Zone Traffic Control Devices

TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)

This work shall be done according to Section 701 of the Standard Specifications and the traffic control plan as shown in the plans and as specified within.

This item shall include the traffic control required for construction of SN 082-0325 under closure, as shown on the construction staging and traffic control plans, except for traffic control and protection paid for separately.

This traffic control and protection will be paid for at the contract unit price per EACH for TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL).

DETOUR SIGNING

This work shall consist of furnishing, installing, maintaining, and removing the detour signage for the temporary ramp closure of WB I-64 to WB I-70. This work shall be according to Section 701 of the Standard Specifications, this provision, and details in the plans.

This work will be measured for payment on a lump sum basis and paid for at the contract unit price per LUMP SUM for DETOUR SIGNING.

Revised 4-16-2025