

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	STU	ITEP STATE
				75% FED / 25% LOCAL	90% STATE / 10% LOCAL
				SAFETY	MULTI-USE PATH
				0021	0028
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	14	14	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	238	238	
73000100	WOOD SIGN SUPPORT	FOOT	36	36	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	282	282	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	550	550	
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	300	300	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8	8	
A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	4	4	
A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	3		3
C2003360	SHRUB, HAMAMELIS VIRGINIANA (COMMON WITCHHAZEL), 5' HEIGHT, BALLED AND BURLAPPED	EACH	2	2	
D2000372	EVERGREEN, JUNIPERUS CHINENSIS MOUNT BATTEN (MOUNTBATTEN CHINESE JUNIPER), 6' HEIGHT, BALLED AND BURLAPPED	EACH	9	9	
K1005863	TREE ROOT PRUNING	EACH	15	15	
X0327036	BIKE PATH REMOVAL	SQ YD	3,600	3,600	

* DENOTES SPECIALTY ITEM

	USER NAME = esdruckrey	DESIGNED - DESIGNED	REVISED - 4/9/2025 	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES					F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 2.0000' / in.	DRAWN - DRAWN	REVISED -							VARIES	17-00064-00-BT	DUPAGE	85	6
	PLOT DATE = 4/9/2025	CHECKED - CHECKED	REVISED -		CONTRACT NO. 61K79									
		DATE - 2/13/2025	REVISED -		SCALE: NTS	SHEET 4	OF 5	SHEETS	STA. N/A	TO STA. N/A	ILLINOIS	FED. AID PROJECT		