

MODEL: Default
FILE: \\na01c-pw\baecom-na-pw-bentley.com\AECOM_DS21_NA_2020\Documents\60632011-IL-471900-CAD\03_SHEETS\Civil\160X17-shr-S00.dgn

				CONSTRUCTION CODE															
				80% FED 20% STATE	80% FED 20% WOODSTOCK	100% WOODSTOCK (MFT)	80% FED 20% STATE	80% FED 20% STATE	100% WOODSTOCK	100% WOODSTOCK	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% WOODSTOCK	100% WOODSTOCK (MFT)	80% FED 20% STATE	80% FED, 10% STATE 10% LOCAL	100% WFRD	80% FED 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY	ROADWAY	SHARED-USE PATH	OHSS	SANITARY	WATER MAIN	RETAINING WALL	LIGHTING (IL 47/US 14/ ROUNDAABOUT)	LIGHTING (OTHER)	LIGHTING (OTHER)	TRAFFIC SIGNALS	TRAFFIC SIGNALS (IL 47/CC RD)	TRAFFIC SIGNALS (EVP)	TRAFFIC SIGNALS (INTERCONNECT)	
				0003	0003	0003	0021	0044	0043	0043	0044	0021	0021	0021	0021	0021	0021	0021	0021
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	S.N. 056-W025	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,304	1,304															
28100109	STONE RIPRAP, CLASS A5	SQ YD	89	89															
28200200	FILTER FABRIC	SQ YD	856	856															
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	19,014	19,014															
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	119,806	119,806															
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	27,009	27,009															
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	23,374	22,110				1,264											
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	11,130				11,130												
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	1,662	1,662															
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	4,293	4,293															
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	42,059	17,026			25,033												
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	17,084	15,020			2,064												
40600370	LONGITUDINAL JOINT SEALANT	FOOT	11,252	11,252															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1.5	1.5															

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM
100% STATE, 0003 URBAN

Ø DENOTES 100% WOODSTOCK (MFT) ITEM

△ 2 REVISED SHEET 4/16/2025



USER NAME = Chiua	DESIGNED - AFC	REVISED -
	DRAWN - AFC	REVISED -
PLOT SCALE = 2.0000 ' / in.	CHECKED - TJW	REVISED -
PLOT DATE = 2/12/2025	DATE - 02/06/2025	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 3 OF 40 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	2024-1052-N,C,SW,FL	MCHENRY	941	7
CONTRACT NO. 62X94				
ILLINOIS FED. AID PROJECT				

MODEL: Default
FILE: \\na1012-pw\baecom-np-ow-bentley.com\AECOM_DS21_NA_2020\Documents\606202011-IL-471900-CAD\03_SHEETS\C\UID.160X17-shr-S00.dgn

				CONSTRUCTION CODE														
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE	80% FED 20% WOODSTOCK	100% WOODSTOCK (MFT)	80% FED 20% STATE	80% FED 20% STATE	100% WOODSTOCK	100% WOODSTOCK	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% WOODSTOCK	100% WOODSTOCK (MFT)	80% FED 20% STATE	80% FED, 10% STATE 10% LOCAL	100% WFRD	80% FED 20% STATE
				ROADWAY	ROADWAY	ROADWAY	SHARED-USE PATH	OHSS	SANITARY	WATER MAIN	RETAINING WALL	LIGHTING (IL 47/U5 14/ ROUNDABOUT)	1 LIGHTING (OTHER)	LIGHTING (OTHER)	TRAFFIC SIGNALS	TRAFFIC SIGNALS (IL 47/CC RD)	TRAFFIC SIGNALS (EVP)	TRAFFIC SIGNALS (INTERCONNECT)
				0003	0003	0003	0021	0044	0043	0043	0044	0021	0028	0021	0021	0021	0021	0021
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	S.N. 056-W025	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
*	78011000	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	1,249	1,249													
*	78011035	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	1,785	1,785													
*	78011040	GROOVING FOR RECESSED PAVEMENT MARKING 8"	FOOT	12,319	12,319													
*	78011050	GROOVING FOR RECESSED PAVEMENT MARKING 10"	FOOT	661	661													
*	78011060	GROOVING FOR RECESSED PAVEMENT MARKING 12"	FOOT	4,625	4,625													
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	367	367													
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	480	480													
	78300201	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	35,339	35,339													
	78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	37,561	37,561													
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	4								4						
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1								1		0				
	81025900	CONDUIT ENCASED, REINFORCED CONCRETE, 4" DIA., PVC 4 WIDE X 1 HIGH	FOOT	540														540
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	12,522												2,570	680	9,272
*	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	650														
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	8,469														
*	81400100	HANDHOLE	EACH	36												9	4	23
*	81400200	HEAVY-DUTY HANDHOLE	EACH	11												9	2	

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM
100% STATE, 0003 URBAN

Ø DENOTES 100% WOODSTOCK (MFT) ITEM

2

REVISED SHEET 4/16/2025

1

REVISED SHEET 4/9/2025



USER NAME = Chiua	DESIGNED - AFC	REVISED -
	DRAWN - AFC	REVISED -
PLOT SCALE = 2.0000 ' / in.	CHECKED - TJW	REVISED -
PLOT DATE = 2/12/2025	DATE - 02/06/2025	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 19 OF 40 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	2024-1052-N,C,SW,FL	MCHENRY	941	23
CONTRACT NO. 62X94				
ILLINOIS FED. AID PROJECT				