

**EROSION CONTROL SCHEDULE**  
**SHEETS ER-02 TO ER-35**

ITEM	20101000	25100127	25100630	25100635	25200110	28000200	28000250	28000305	28000400	28001000	72000200	X2800520
	TEMPORARY FENCE	MULCH, METHOD 3A	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	SODDING, SALT TOLERANT	EARTH EXCAVATION FOR EROSION CONTROL	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	AGGREGATE (EROSION CONTROL)	SIGN PANEL - TYPE 2	ABOVE GRADE INLET FILTERS
SHEET	FOOT	ACRE	SO YD	SQ YD	SO YD	CU YD	POUND	FOOT	FOOT	TON	SO FT	EACH
ER-02	0	1.00	0	0	0	0	100.00	0	136	0	0	5
ER-03	1,332	0.50	0	0	85	5	55.75	0	100	6	54	6
ER-04	965	1.00	78	0	0	185	105.75	0	2,340	8	54	51
ER-05	609	1.00	107	0	0	320	109.75	0	2,198	16	54	35
ER-06	220	1.50	49	0	1265	80	153.25	52	867	7	18	28
ER-07	0	0.00	0	0	811	0	0.00	20	0	0	0	2
ER-08	0	0.75	98	6232	0	300	211.00	290	0	8	0	17
ER-09	202	0.50	137	5370	0	510	172.75	150	2,103	19	0	51
ER-10	0	0.25	54	7153	0	140	177.25	850	1,629	7	0	58
ER-11	0	0.25	0	4341	0	0	114.75	450	1,025	0	0	41
ER-12	0	0.50	73	3868	0	160	134.25	30	1,986	29	0	41
ER-13	0	0.00	0	100	0	0	0.00	0	59	0	0	1
ER-14	0	0.00	0	0	0	0	0.00	0	0	0	0	8
ER-15	0	0.00	0	0	0	0	0.00	0	0	0	0	14
ER-16	0	0.00	0	0	0	0	0.00	0	0	0	0	15
ER-17	0	0.00	0	0	0	0	0.00	0	0	0	0	14
ER-18	0	0.00	0	0	0	0	0.00	0	0	0	0	17
ER-19	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-20	0	1.75	0	2907	519	0	94.25	300	0	0	0	14
ER-21	0	0.25	200	5775	815	207	102.50	60	2,154	6	0	51
ER-22	0	1.00	0	0	0	0	0.00	0	0	0	0	50
ER-23	0	1.00	0	863	0	0	25.00	0	0	0	0	49
ER-24	0	1.00	45	0	1210	80	25.00	30	476	0	0	45
ER-25	0	0.00	0	0	757	0	0.00	20	0	0	0	1
ER-26	0	0.00	0	0	0	0	0.00	0	0	0	0	8
ER-27	0	0.00	0	0	0	0	0.00	0	0	0	0	13
ER-28	0	0.00	0	0	0	0	0.00	0	0	0	0	14
ER-29	0	0.00	0	0	0	0	0.00	0	0	0	0	12
ER-30	0	0.00	0	0	0	0	0.00	0	0	0	0	16
ER-31	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-32	0	0.50	0	0	0	0	25.00	0	979	0	0	1
ER-33	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-34	0	0.25	0	107	0	0	27.25	0	345	23	0	0
ER-35	0	0.25	0	0	0	0	25.00	0	0	0	0	0

NOTE:  
FOR EROSION CONTROL SCHEDULE SHEETS ER-36 TO ER-62 AND TOTAL QUANTITIES, SEE SHEET SC-05.

**APX**  
CONSULTING ENGINEERS, L.L.C.  
311 E. Wacker Drive, Suite 528  
Chicago, IL 60601

FILE NAME : *FILE*	USER NAME : *USER*	DESIGNED - R.A.D.	REVISED - $\Delta$ 04/12/2013	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>EROSION CONTROL SCHEDULE OF QUANTITIES SOUTH CONTRACT</b>	F.A.P. RTE. 330	SECTION 103R-3	COUNTY COOK	TOTAL SHEETS 932	SHEET NO. 48
PLOT SCALE : *SCALE*	CHECKED - W.H.I.	REVISED -	REVISED -			<b>SC-04</b>		CONTRACT NO. 60F05		
PLOT DATE : *DATE*	DATE - 03/15/2013	REVISED -	REVISED -			SCALE: N.T.S.	SHEET NO. 4 OF 5 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	