

**EROSION CONTROL SCHEDULE
SHEETS ER-36 TO ER-62**

ITEM	20101000	25100127	25100630	25100635	25200110	28000200	28000250	28000305	28000400	28001000	72000200	X2800520
	TEMPORARY FENCE	MULCH. METHOD 3A	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	SODDING, SALT TOLERANT	EARTH EXCAVATION FOR EROSION CONTROL	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	AGGREGATE (EROSION CONTROL)	SIGN PANEL - TYPE 2	ABOVE GRADE INLET FILTERS
SHEET	FOOT	ACRE	SO YD	SO YD	SO YD	CU YD	POUND	FOOT	FOOT	TON	SQ FT	EACH
ER-36	0	0.00	0	107	0	0	2.25	0	0	0	0	0
ER-37	0	0.25	0	0	0	0	34.25	0	1,109	0	0	15
ER-38	0	0.25	0	0	0	0	34.25	0	318	0	0	8
ER-39	0	0.00	0	0	0	0	1.00	0	245	0	0	4
ER-40	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-41	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-42	0	0.00	0	0	0	0	25.00	0	0	0	0	0
ER-43	0	0.25	0	0	0	0	25.00	0	0	0	0	0
ER-44	0	0.50	0	0	0	0	50.00	0	0	0	0	5
ER-45	0	0.00	0	125	0	0	2.75	0	0	0	0	1
ER-46	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-47	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-48	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-49	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-50	0	0.50	0	0	0	0	50.00	0	710	0	0	2
ER-51	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-52	0	0.25	0	608	0	0	25.00	0	664	0	0	4
ER-53	0	0.00	0	0	0	0	3.00	0	0	0	0	6
ER-54	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-55	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-56	0	0.25	0	0	0	0	25.00	0	0	0	0	0
ER-57	0	0.25	0	0	0	0	25.00	0	0	0	0	0
ER-58	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-59	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-60	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-61	0	0.25	0	0	0	0	25.00	0	0	0	0	4
ER-62	0	0.25	0	0	0	0	25.00	0	0	0	0	4
ER-63	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-64	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-65	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-66	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-67	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-68	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-69	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-70	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-71	0	0.00	0	0	0	0	0.00	0	0	0	0	0
SUB TOTAL	3,328	16.25	841	37,556	5,462	1,987	2,011.00	2,252	19,443	129		731
AT THE ENGINEER'S DISCRETION	333	1.75	84	3,756	546	199	201.00	225	1,944	13		73
GRAND TOTAL	3,661	18.00	925	41,312	6,008	2,186	2,212	2,477	21,387	142	180	804

NOTE: FOR EROSION CONTROL SCHEDULE SHEETS ER-02 TO ER-35, SEE SHEET SC-04.

APEX
CONSULTING ENGINEERS, LLC
111 N. Wacker Drive, Suite 508
Chicago, IL 60601

FILE NAME :

#FILE#

USER NAME : #USER#

PLOT SCALE : #SCALE#

PLOT DATE : #DATE#

DESIGNED - R.A.D.

DRAWN - L.N.

CHECKED - W.H.I.

DATE - 03/15/2013

REVISED - Δ 04/12/2013

REVISED -

REVISED -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**EROSION CONTROL SCHEDULE OF QUANTITIES
SOUTH CONTRACT**

SCALE: N.T.S. SHEET NO. 5 OF 5 SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 103R-3	COUNTY COOK	TOTAL SHEETS 932	SHEET NO. 49
SC-05			CONTRACT NO. 60F05	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		