


* = SPECIALTY ITEMS, ** 80% FED, 10% STATE, 10% OP
 OP=VILLAGE OF ORLAND PARK, OH=VILLAGE OF ORLAND HILLS,
 TP=VILLAGE OF TINLEY PARK

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 179TH	TRAFFIC SIGNALS 171ST	TRAFFIC SIGNALS 167TH	TRAFFIC SIGNALS 163RD	INTERCONNECT	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	TINLEY PARK 100%	WATER MAIN/FIBER OPTIC/EVP	WATER MAIN/SAN SEWER	RETAINING WALLS
				80% FED 20% STATE	100% OP	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	**	80% FED 20% STATE	80% FED 20% OP	80% FED 20% OH	80% FED 20% TP	100% TP	100% OP	100% TP	80% FED 20% STATE
				0003	0021	0021	0021	0021	0021	0021	0028	0028	0028	0031	0043	0043	0040
X0325003	REMOVE EXISTING VALVE AND VAULT	EACH	2	2													
X6020090	MANHOLES, TYPE A, 6' -DIAMETER, WITH 2 TYPE 1 FRAME, OPEN LIDS, RESTRICTOR PLATE <i>closed</i>	EACH	11	11													
X0325318	LIGHTWEIGHT CELLULAR CONCRETE FILL	CU YD	1600														1600
* X0325751	DRIVING SOLDIER PILES	FOOT	632														632
* X0326498	GFCI 20 AMP DUPLEX RECEPTACLE	EACH	35		35												
X0326747	SANITARY FORCE MAIN, 6"	FOOT	735	735													
* X0327004	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	1		1												
X0327024	FIRE HYDRANTS TO BE REMOVED & SALVAGED	EACH	4	2													2
X0327482	TAPPING VALVES AND SLEEVES, 8"X8", IN 60" DIAMETER VALVE VAULT, TYPE 1 FRAME, CLOSED LID	EACH	2	1													1
X0327483	TAPPING VALVES AND SLEEVES, 12"X12", IN 60" DIAMETER VALVE VAULT, TYPE 1 FRAME, CLOSED LID	EACH	1														1
X2800520	ABOVE GRADE INLET FILTERS	EACH	8	8													
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4	4													
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	36	36													
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1													



FILE NAME : D168F05-SHT-S00.dgn
 USER NAME : Frank.Stallone
 DESIGNED -
 DRAWN -
 CHECKED -
 PLOT DATE : 2/6/2013

REVISOR -
 REVISIONS -
 REVISIONS -
 REVISIONS -
 REVISIONS -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE: SHEET 24 OF 32 SHEETS STA. TO STA.

F.A.P. RTE. 330 SECTION 103R-3 COUNTY COOK TOTAL SHEETS 932 SHEET NO. 28 CONTRACT NO. 60F05 ILLINOIS FED. AID PROJECT