

***= ORLAND FIRE PROTECTION DISTRICT
 **= SPECIALTY ITEMS, ** 80% FED, 10% STATE, 10% OP
 OP=VILLAGE OF ORLAND PARK, OH=VILLAGE OF ORLAND HILLS,
 TP=VILLAGE OF TINLEY PARK

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 179TH	TRAFFIC SIGNALS 171ST	TRAFFIC SIGNALS 167TH	TRAFFIC SIGNALS 163RD	INTERCONNECT	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	NEW SIDEWALK /BIKE PATH	TINLEY PARK 100%	WATER MAIN/FIBER OPTIC/EVP	WATER MAIN/SAN SEWER	RETAINING WALLS
				80% FED 20% STATE	100% OP	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	**	80% FED 20% STATE	80% FED 20% OP	80% FED 20% OH	80% FED 20% TP	100% TP	100% OP	100% TP	80% FED 20% STATE
				0003	0021	0021	0021	0021	0021	0021	0028	0028	0028	0031	0043	0043	0040
* X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	1		1												
* X8360215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	45		45												
* X8300001	LIGHT POLE, SPECIAL	EACH	35		35												
* X8300005	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, SPECIAL	EACH	32		32												
* X8510200	PAINT TRAFFIC SIGNAL EQUIPMENT	L SUM	1												1		
* X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	4			1	1	1	1								
* X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	4			1	1	1	1								
* X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	15,639							15,639							
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	3908											2201	1707***		
* X8950075	REMOVE EXISTING LIGHTING CONTROLLER AND SALVAGE	EACH	2		2												
* X8950600	REMOVE AND RELOCATE EXISTING LIGHT STANDARD	EACH	4		4												
XX000052	REMOVE EXISTING WATER MAIN 12 INCH	FOOT	1176	550													626
XX000541	EXPLORATORY EXCAVATION	CU YD	100	100													
XX003885	IRRIGATION SYSTEM	L SUM	1														1
XX005713	ORNAMENTAL RAILING	FOOT	2418											361	848		1209
* XX005937	LED INTERNALLY ILLUMINATED STREET NAME SIGN	EACH	8												8		
* XX006653	FENCE, SPECIAL	FOOT	556											556			

URS
 100 S. WACKER DR.
 SUITE 500
 CHICAGO, IL 60606
 TEL 312-433-1000
 FAX 312-433-1058

FILE NAME : D:\60F05-SHT-500.dgn	USER NAME : Frank.Stallone	DESIGNED -	REVISED -
SHT PLAN	PLOT SCALE = 100,0000' / 1" IN.	DRAWN -	REVISED -
	PLOT DATE = 2/6/2013	CHECKED -	REVISED -
		DATE - 02/07/13	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 27 OF 32 SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 103R-3	COUNTY COOK	TOTAL SHEETS 932	SHEET NO. 31
CONTRACT NO. 60F05			ILLINOIS FED. AID PROJECT	

Rev.