DRAWING NUMBER	STATION	OFFSET LT/RT	SIGN TYPE	SIGN SIZE WIDTH (INCHES)	SIGN SIZE DEPTH (INCHES)	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN SUPPORT TYPES NO POST	METAL POST TYPE A	METAL POST TYPE B	WOOD POST	RELOCATE EXISTING SIGNS EACH	REMOVE & RE-ERECT EX SIGN EACH
LA-01	20+57	RT-MED	SPEC										1
	25+10	RT-MED	R3-5L	30	36	7.5		2	28				
LA-01	29+50	LT	R2-1	30	36	7.5	-	2	28	-	-	-	-
	31+07	LT	W4-3R	36	36	9		2	28				
	32+50	RT	R3-5R	30	36	7.5		2	28				
	33+20	LT	M3-3	24	12	2		1		14			
			M1-4	24	24	4							
	35+14	LT-MED	R4-7	24	30	5		1		14			
			R3-8LL	36	36	9							
	36+71	RT-MED	R4-7	24	30	5		1		14			
			R3-8CUL	24	30	5							
	37+38	RT	M3-1	24	12	2		1		14			
			M1-4	24	24	4							
	40+50	RT	R2-1	30	36	7.5		2	28				
LA-02	52+89	LT	W1-2	36	36	9		2	28				
	54+16	RT	W2-2R	36	36	9		2	28				
			W16-8P	30	9	1.88							
	60+10	LT	R2-1	30	36	7.5		2	28				
	62+05	LT-MED	R3-8U	24	30	5		1		14			
			R4-7	24	30	5							
	63+28	RT-MED	R3-5L	24	30	5		1		14			
			R4-7	24	30	5							
	62+71	LT	W1-7	48	24	8		2	26				
	63+03	RT	D3-1	48	18	6.00		LP					
			D3-1	42	30	8.75							
	63+60	RT	SPEC					1		15		1	
	63+00	RT	R1-1	36	36	9.00		2	28				
	66+83	RT	R1-1	30	30	6.25		1		14			
LA-03	74+22	RT	R1-1	30	30	6.25		1		14			
	74+58	LT	W2-2L	36	36	9		2	30				
			W16-8P	30	9	1.88							
	78+84	LT	R2-1	30	36	7.5		2	28				
	78+98	RT	R2-1	30	36	7.5		2	28				
	81+83	RT	D3-1	42	18	5.25		2	28				
	84+65	RT	R3-5R	30	36	7.5		2	28				
	86+43	RT	R1-1	30	30	6.25		1		14			
	88+37	LT-MED	R3-8U	24	30	5		1		14			
			R4-7	24	30	5							
	87+20	LT	M3-3	24	12	2.00		1		14			
			M1-4	24	24	4							
	89+29	LT	W1-7	48	24	8		2	26				
	89+90	RT-MED	R4-7	24	30	5		2	28				
			R3-8LL	36	36	9							
	90+19	RT	M3-1	24	12	2.00		1		14			
			M1-4	24	24	4							
	91+50	RT	R2-1	30	36	7.5		2	28				
	94+85	LT	D3-1	42	18	5.25		2	24				
LA-04	109+47	RT	D3-1	48	18	6.00		2	24				
	111+13	LT	R2-1	30	36	7.5		2	28				
	111+47	RT	R1-1	30	30	6.25		1		14			
	112+58	LT	M3-3	24	12	2.00		1		14			
			M1-4	24	24	4							
	114+99	LT	M1-4	24	24	4		1		15			
			M6-4	21	15	2.19							
	115+10	LT-MED	R4-7	24	30	5		1		15			
			R3-8CUL	24	30	5							
	SUB-TOTAL1					311	0		578	241	0	1	1

DRAWING NUMBER	STATION	OFFSET LT/RT	SIGN TYPE	SIGN SIZE WIDTH (INCHES)	SIGN SIZE DEPTH (INCHES)	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN SUPPORT TYPES NO POST	METAL POST TYPE A	METAL POST TYPE B	WOOD POST	RELOCATE EXISTING SIGNS EACH	REMOVE & RE-ERECT EX SIGN EACH
	116+40	RT-MED	R4-7	24	30	5		1		15			
			R3-8CUL	24	30	5							
	116+61	RT	M3-1	24	12	2		1		14			
			M1-4	24	24	4							
LA-04	118+24	RT	R2-1	30	36	7.5	-	2	28	-	-	-	-
	121+76	RT	SPEC			0		1	14			1	
	123+74	RT	SPEC			0		1	14			1	
	126+06	LT	R2-1	30	36	7.5		2	28				
	128+54	LT-MED	R4-7	24	30	5		2		28			
			R3-8CUL	24	30	5							
	128+72	LT	R1-1	36	36	9		2	28				
	128+92	RT	W1-7	48	24	8		2	26				
	129+50	LT-MED	R4-7	24	30	5		1		14			
			R3-8U	24	30	5							
	129+41	LT	D3-1	66	18	8.25		LP					
			D3-1	48	18	6							
LA-05	135+90	RT	D3-1	48	18	6		2	24				
	138+95	LT	R2-1	30	36	7.5		2	28				
	139+78	LT	M3-3	24	12	2		1		14			
			M1-4	24	24	4							
	139+74	LT-MED	R4-7	24	30	5		1		14			
			R3-8CUL	24	30	5							
	141+40	RT-MED	R4-7	24	30	5		2	28				
			R3-8ULL	36	36	9							
	141+68	RT	M3-1	24	12	2		1		14			
			M1-4	24	24	4							
	143+50	RT	R2-1	30	36	7.5		2	28				
	145+86	RT	R1-1	30	30	6.25		1		14			
	146+27	LT	R1-1	30	30	6.25		1		14			
	153+82	LT-MED	R4-7	24	30	5		1		14			
			R3-8CUL	24	30	5							
	153+91	LT	R1-1	30	30	6.25		1		14			
	154+75	RT	R1-1	30	30	6.25		1		14			
	154+95	RT-MED	R4-7	24	30	5		1		14			
			R3-8CUL	24	30	5							
	159+94	RT	M2-1	30	21	4.38		2		34			
			M1-4	36	36	9							
			D3-2	36	9	2.25							
LA-06	162+80	RT	R2-1	30	36	7.50		2	28				
	163+30	LT	R2-1	30	36	7.50		2	28				
	165+90	LT-MED	SPEC										1
	166+23	LT-MED	SPEC										1
	167+93	LT-MED	SPEC										1
LA-07	902+20	LT	W1-8	12	18	1.50		1	12				
179TH ST	903+30	LT	W1-8	12	18	1.50		1	12				
	904+09	RT	W3-3	36	36	9		2	28				
	904+40	LT	W1-8	12	18	1.50		1	12				
	904+50	RT	R3-8b	48	30		10	2	26				
	905+45	LT	W8-HE	36	36	9		2	32				
			W16-2	24	18	3							
	905+45	RT	D3-2	72	30		15	2			30		
	905+96	RT	R3-7R	30	30	6.25		1		14			
	907+13	RT	R3-5R	30	36	7.5		2	28				
	907+45	LT	W9-2L	36	36	9		2	28				
	SUB-TOTAL2					264	25		480	245	30	2	3

NOTE:
SIGN PANELS MOUNTED TO MAST ARMS
ARE NOT INCLUDED IN THIS SCHEDULE

URS
100 S. WACKER DR.
SUITE 500
CHICAGO IL 60606
TEL (312)939-1000
FAX (312)939-9498

FILE NAME = D160F05-SHT-SCHEDULE02.dgn	USER NAME = Anthony.Plutz	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.000091 ' / in.	CHECKED -	REVISED -
SHT_PLAN	PLOT DATE = 3/14/2013	DATE - 03/13/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. | SHEET 2 OF 5 SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	103R-3	COOK	932	46
	SC-02	CONTRACT NO. 60F05		
	ILLINOIS	FED. AID PROJECT		