STA 22+51.21
MATCH EXISTING

PCC SHOULDER, 10''

OUTLET FOR CONCRETE CURB & GUTTER, TYPE B-6.24
PAID FOR AS CLASS SI CONCRETE, OUTLET

COMB CONC CURB & GUTTER
TYPE B-6.24 (TYPICAL)

PAVEMENT WIDENING
SEE TYPICAL SECTION
DRAWING TS-01

DRILL AND GROUT WITH
NO. 6 TIE BARS AT 24'' CTS

END PAVEMENT WIDENING
BEGIN PAVEMENT RECONSTRUCTION
STA 27+49.31
MATCH EXISTING

12.5'
2.5%

22+51.21
44.83' LT

22+94.49
57.32' LT

MATCH EXISTING PAVEMENT

25+57.73
41.75' LT

12.5'
2.5%

27+49.31
38.73' LT

71.2'

35.4'

COMB CONC CURB & GUTTER
TYPE B-6.18 MOD (TYPICAL)

23+78.71
8.18' RT
PT

℄ US 45 (LaGRANGE RD)

26+22.54
4.72' LT

27+49.31
3.22' LT

22 | 23 | 24 | 25+00 | 26 | 27

22+96.53
13.39' RT

US 45 (LAGRANGE RD)

29.6'

CONCRETE MEDIAN
TYPE SB-6.18

23+78.85
20.18' RT

LANDSCAPE MEDIAN
SEE LANDSCAPING PLANS

35.6'

27+49.31
26.34' RT

35.5'

27+49.31
61.94' RT

SEE DRAWING PP-01
MATCH LINE STA. 21+50.00

MATCH LINE STA. 27+50.00
SEE DRAWING PP-03

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
RT. OF WAY CHECKED
CADD FILE NAME
NOTE BOOK
NO.
BY
DATE

PROFILE
SURVEYED
PLOTTED
CROSS SECT. CHECKED
B.M. NOTED
STRUCTURE NOTATNS CHKD
NOTE BOOK
NO.
BY
DATE

750
745
740
735
730
725

PAVEMENT WIDENING
PROJECT LIMITS
STA 22+51.21

STA 27+49.31
MATCH EXISTING
US 45 PAVEMENT

743.33

EXISTING GROUND LINE
℄ US 45

735.44 | 736.00 | 736.63 | 737.24 | 737.90 | 738.65 | 739.37 | 740.01 | 740.68 | 741.82 | 742.48 | 743.07 | 743.64 | 743.34

21+50 | 22+00 | 22+50 | 23+00 | 23+50 | 24+00 | 24+50 | 25+00 | 25+50 | 26+00 | 26+50 | 27+00 | 27+50

URS
100 S. WACKER DR.
SUITE 900
CHICAGO, IL 60606
TEL (312)939-1000
FAX (312)939-498

FILE NAME = D160F05-SHT-PLNPRF02.dgn	USER NAME = Frank_Stallone	DESIGNED - JTF	REVISED -
		DRAWN - JTF	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED - MJT	REVISED -
SHT_PLNPROF URBAN	PLOT DATE = 3/14/2013	DATE - 03/13/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PROPOSED PLAN AND PROFILE – US 45 (LAGRANGE ROAD)

SCALE:1''=20'H;1''=5'V | SHEET 2 OF 26 SHEETS | STA. BEGIN TO STA. 27+50.00

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	103R-3	COOK	932	71
	PP-02	CONTRACT NO. 60F05		
	ILLINOIS FED. AID PROJECT			