



47 HANDHOLE
 STA 162+77, 57.6' LT
 N 1797083.62
 E 1115623.81

PROP 4" PVC CONDUIT
 FOR FUTURE FIBER OPTIC

STA 165+00
 END SEGMENT 1 CONTRACT
 CONNECT TO SEGMENT 2
 CONDUIT. IF COMPLETED,
 OR CAP

R.O.W.

SEE DRAWING FIBOP-05
 MATCH LINE STA. 162+00.00

US ROUTE 45 (LAGRANGE ROAD)

US ROUTE 45 (LAGRANGE ROAD)

159TH STREET

159TH STREET

RESTORATION OF WORK AREA, RESTORATION OF THE TRAFFIC SIGNAL
 WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS
 FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND
 NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES
 SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL
 BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE
 REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED
 FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD
 SPECIFICATIONS 252 AND 250 RESPECTIVELY.

NOTE:
 GALVANIZED STEEL CONDUIT IDENTIFIED AS IN TRENCH (T) OR
 PUSHED (P) IS SHOWN FOR INFORMATION ONLY. ALL UNDERGROUND
 CONDUIT SHALL BE PAID FOR AT THE CONTRACT UNIT PRICER PER
 FOOT FOR UNDERGROUND CONDUIT, OF THE TYPE AND SIZE SPECIFIED,
 REGARDLESS OF THE METHOD OF INSTALLATION.

100 S. WACKER DR.
 SUITE 600
 CHICAGO, IL 60606
 TEL (312) 939-1000
 FAX (312) 939-4198



FILE NAME = D160F05-SHT-FIBOP06.dgn	USER NAME = Anthony.Plutz	DESIGNED - BA	REVISED -
		DRAWN - BA	REVISED -
	PLOT SCALE = 100.000000' / in.	CHECKED - MJT	REVISED -
SHT_DOUBLE PLAN	PLOT DATE = 3/12/2013	DATE - 03/13/13	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

PROPOSED FIBER OPTIC CONDUIT US 45 (LAGRANGE ROAD) FROM 183RD STREET TO 159TH STREET			
SCALE: 1"=50'	SHEET 6 OF 6 SHEETS	STA. 162+00.00 TO STA. END	

F.A.P. RTE. 330	SECTION 103R-3	COUNTY COOK	TOTAL SHEETS 932	SHEET NO. 376
FIBOP-06			CONTRACT NO. 60F05	
ILLINOIS FED. AID PROJECT				