


SUMMARY OF QUANTITIES		UNIT	CONSTRUCTION CODE					
CODE NO.	ITEM DESCRIPTION		URBAN 90% FED. 10% STATE TOTAL	0003 RDWY	0010 BRIDGE	0021 SIGNALS LIGHTING	0031 LNDS CP	0040 RET. WALL
60500070	REMOVING MANHOLES TO MAINTAIN FLOW	EACH	12	12				
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	5	5				
60602800	CONCRETE GUTTER, TYPE B	FOOT	610.0	610.0				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	4,371.0	4,371.0				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	5,092.0	5,092.0				
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	73.0	73.0				
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	112.0	112.0				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	7,947	7,947				
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	34	34				
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	9,825	9,825				
60624600	CORRUGATED MEDIAN	SQ FT	590	590				
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1,212.5			1,212.5		

* SPECIALTY ITEM

 PATRICK ENGINEERING INC. 4970 VARSITY DRIVE LISLE, IL 60532 patrickengineering.com	USER NAME = kroeppen@dwg.Lisite PLOT CONFIG = PDF (Gray_Small).plt PLOT SCALE = 1:180 PLOT DATE = 2/18/2013 4:37:58 PM	DESIGNED - CPK DRAWN - MJP CHECKED - JAH DATE = 2/18/2013	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE. 2746	SECTION 1616B	COUNTY COOK	TOTAL SHEETS 404	SHEET NO. 14
	SCALE: NA	SHEET S00-11 OF 36	STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	60J14						