


SUMMARY OF QUANTITIES		UNIT	URBAN ADJ. FED. 10% STATE TOTAL	CONSTRUCTION CODE				
CODE NO.	ITEM DESCRIPTION			0003 RDWY	0010 BRIDGE	0021 SIGNALS LIGHTING	0031 LNDSCP	0040 RET. WALL
* X0322445	TONE EQUIPMENT MOUNTING FRAME	EACH	4			4		
* X0322446	CABINET HOUSING EQUIPMENT, TYPE III	EACH	4			4		
* X0322689	POLE, STEEL, ANCHOR BASE, 10" DIA., 7-GAUGE, 34'-6"	EACH	3			3		
* X0322690	POLE, STEEL, ANCHOR BASE, 10" DIA., 3-GAUGE, 34'-6"	EACH	3			3		
* X0322713	FLASHING BEACON, BRACKET MOUNTED	EACH	2			2		
* 81028730	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/4" DIA.	FOOT	355			355		
X0323160	VIDEO INSPECTION OF STORM SEWER	FOOT	12,221	12,221				
* X0324571	MAINTENANCE OF STREET LIGHTING SYSTEM (CITY OF CHICAGO)	L SUM	1			1		
* X0326326	CABLE IN CONDUIT, TRIPLEX, 2-1/C NO. 6 AND 1-1/C NO. 8 GROUND	FOOT	5,266			5,266		
X0326401	BARRIER WALL REMOVAL	FOOT	185		185			
* X0326451	VIDEO SYSTEM DETECTION CAMERA	EACH	12			12		
X0326694	PLUG EXISTING STORM SEWERS	CU YD	1	1				

* SPECIALTY ITEM

 PATRICK ENGINEERING INC. 4970 VARSITY DRIVE LISLE, IL 60532 patrickengineering.com	USER NAME = kwoopen@rdg.lisle PLOT CONFIG = PDF Gray_Small p1t PLOT SCALE = 1/8"=1'-0" PLOT DATE = 2/18/2013 4:39:27 PM	DESIGNED - CPK DRAWN - MJP CHECKED - JAH DATE - 2/18/2013	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE. 2746 SECTION 1616B COUNTY COOK FEDERAL AID PROJECT	TOTAL SHEETS 404 SHEET NO. 29 60J14
	SCALE: NA SHEET 500-26 OF 36 STA. TO STA.	ILLINOIS FED. AID PROJECT							

Rev.