


SUMMARY OF QUANTITIES		UNIT	TOTAL	CONSTRUCTION CODE				
CODE NO.	ITEM DESCRIPTION			0003 RDWY	0010 BRIDGE	0021 SIGNALS LIGHTING	0031 LNDSCP	0040 RET. WALL
* X0326968	JUNCTION BOX, POLE OR POST MOUNTED	EACH	33			33		
* X0327392	WOOD POLE, 60 FT., CLASS 4	EACH	9			9		
X2020502	BRACED EXCAVATION	CU YD	87		87			
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1,274		1,047			227
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	200	200				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	3	3				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5	5				
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1				
X4240430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	1,521	1,521				
X4403700	MEDIAN REMOVAL (SPECIAL)	SQ FT	6,048	6,048				
X5030272	BRIDGE DECK (SHRINKAGE REDUCING ADMIXTURE)	CU YD	966.6		966.6			
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	57	57				

LRBON
907. FED.
10/STATE
TOTAL

• SPECIALTY ITEM

 PATRICK ENGINEERING INC 4970 VARSITY DRIVE LISLE, IL 60532 patrickengineering.com	USER NAME = koeppen@dwg.Lisale PLOT CONFIG = PDF(Gray_Small).plt PLOT SCALE = 1:1000 PLOT DATE = 2/18/2013 4:39:32 PM	DESIGNED - CPK DRAWN - MJP CHECKED - JAH DATE - 2/18/2013	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE. 2746	SECTION 1616B	COUNTY COOK	TOTAL SHEETS 404	SHEET NO. 30
	SCALE: NA SHEET 500-27 OF 36 STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT 60J14									