


SUMMARY OF QUANTITIES		UNIT	URBAN 90% FED. 10% STATE TOTAL	CONSTRUCTION CODE				
CODE NO.	ITEM DESCRIPTION			0003 RDWY	0010 BRIDGE	0021 SIGNALS LIGHTING	0031 LNDSCP	0040 RET. WALL
* A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3				3	
* A2006520	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6				6	
* A2006572	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 9' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	6				6	
X6020270	MANHOLE, TYPE B, TYPE 1 FRAME, CLOSE LID (CITY OF CHICAGO) 4' DIA.	EACH	1	1				
* X0370046	ELECTRIC CABLE IN CONDUIT NO 2 3/C (CDOT)	FOOT	776			776		
* X0370047	INSTALL LIGHT POLE, MAST ARM, AND LUMINAIRE (CHICAGO)	EACH	7			7		
* X8440116	RELOCATE EXISTING LIGHTING UNIT, SPECIAL	EACH	10			10		
* X0370048	SERVICE INSTALLATION, 200 AMPERE (CDOT)	EACH	2			2		
* X0370049	UNDERGROUND CONDUIT, PVC, 2" DIA., SCHEDULE 80 (CDOT)	FOOT	96			96		
* X8301040	MAST ARM, ALUMINUM, 10 FT.	EACH	8			8		
* X8301042	MAST ARM, ALUMINUM, 12 FT.	EACH	2			2		
* X0327586	REMOVE AND REPLACE FUSE KIT	EACH	92			92		

* SPECIALTY ITEM

 PATRICK ENGINEERING INC 4970 VARSITY DRIVE LISLE, IL 60532 patrickengineering.com	USER NAME - tkoepfani@eng.lisle PLOT CONFIG - PDFtoGray_Small.plt PLOT SCALE - 1:1000 PLOT DATE - 2/18/2013 4:40:00 PM	DESIGNED - CPK DRAWN - MJP CHECKED - JAH DATE - 2/18/2013	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES			F.A.U. RTE. 2746	SECTION 1616B	COUNTY COOK	TOTAL SHEETS 404	SHEET NO. 35
					SCALE: NA	SHEET 500-32 OF 36	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		60J14			