


SUMMARY OF QUANTITIES		UNIT	URBAN 90% FED. 10% STATE TOTAL	CONSTRUCTION CODE					
CODE NO.	ITEM DESCRIPTION			0003	0010	0021	0031	0040	
				RDWY	BRIDGE	SIGNALS LIGHTING	LNDSCP	RET. WALL	
	<i>ADVANCED TRANSPORTATION</i>								
X0370050	CONTROLLER, TRAFFIC, 16 LOAD BAY, "P" CABINET (CDOT)	EACH	4			4			
X0370010	COAXIAL JUMPER CABLE (CDOT)	EACH	4			4			
X0370013	CONCRETE FOUNDATION FOR TYPE "P" BASE MOUNTED TRAFFIC SIGNAL CONTROLLER (CDOT)	EACH	4			4			
X0370014	CONCRETE FOUNDATION, 20" DIAMETER, 3/4" ANCHOR RODS, 13" BOLT CIRCLE (CDOT)	EACH	1			1			
X0370068	CONCRETE FOUNDATION, 24" DIAMETER, 1 1/4" ANCHOR RODS, 15" BOLT CIRCLE (CDOT)	EACH	1			1			
X0370015	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/2" ANCHOR RODS, 16 1/2" BOLT CIRCLE (CDOT)	EACH	1			1			
X0370016	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/4" ANCHOR RODS, 17 1/4" BOLT CIRCLE (CDOT)	EACH	1			1			
X0370051	CUT OFF POLE AND INSTALL CAP (CDOT)	EACH	1			1			
X0370018	ELECTRIC CABLE IN CONDUIT NO. 14 19/C (CDOT)	FOOT	5,288			5,288			
X0370052	ELECTRIC CABLE IN CONDUIT NO. 4 2/C (CDOT)	FOOT	577			577			
X0370053	ELECTRIC CABLE NO. 14 3/C, SHIELDED (CDOT)	FOOT	2,471			2,471			
X0370021	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID (CDOT)	EACH	4			4			

\* SPECIALTY ITEM

 PATRICK ENGINEERING INC 4970 VARSITY DRIVE LISLE, IL 60532 pat@patrickengineering.com	USER NAME = kwoepfen@dwg.Lisle1 PLOT CONFIG = PDFtoGray_Small.plt PLOT SCALE = 1:100 PLOT DATE = 2/18/2013 4:48:05 PM	DESIGNED - CPK DRAWN - MJP CHECKED - JAH DATE - 2/18/2013	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.U. RTE. 2746	SECTION 1616B	COUNTY COOK	TOTAL SHEETS 404	SHEET NO. 36
	SCALE: NA	SHEET 500-33 OF 36	STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	60J14						