

NOT TO SCALE

6" (150 mm) X 6" (150 mm) X 16' (5.0 m)
WOOD POST

FLEXIBLE METAL CONDUIT
IN HOLE DRILLED THROUGH
WOOD POST

1 1/2 IN. (38.0 mm) GS-CONDUIT

FLEXIBLE METAL CONDUIT
IN HOLE DRILLED THROUGH
WOOD POST

2FT. (600 mm) MIN

5"
(130 mm)

1'-1.5"
(343 mm)

4'-6"
(1.4 m)

6'-0"
(1.80 m)

ADJUSTABLE ONE SECTION 8" (203 mm)
BEACON WITH AMBER LENS

6" (150 mm) X 6" (150 mm) X 16' (5.0 m)
WOOD POST

5" (130 mm)

A

SIGN TO BE PLACED BY STATE

A

6'-0"
(1.80 m)

NOTE:

- 1) SIGN WILL BE PLACED ON THE FRONT FACE OF WOOD POST BY STATE. 4'-6" (1.4 m) DIMENSION MUST BE KEPT FREE OF CONDUIT AND CONNECTIONS TO PREVENT INTERFERENCE WITH SIGN PLACEMENT.
- 2) WOOD POST SHALL NOT BE SET IN CONCRETE (REFER TO SPECIAL PROVISIONS).
- 3) A CLEAR LAMP ESPECIALLY DESIGNED FOR TRAFFIC SIGNAL SERVICE SHALL BE RATED AT 67 WATTS, 120 VOLTS.

| | | | |
|---|-------------------------------|-----------------|-----------------|
| FILE NAME = | USER NAME = mezag | DESIGNED - R.L. | REVISED - 09/96 |
| et:\pw\work\p1dot\mezag\d0287541\TSCTYP.dgn | | DRAWN - G.M. | REVISED - |
| | PLOT SCALE = 100.0000' / 1in. | CHECKED - R.L. | REVISED - |
| | PLOT DATE = 7/26/2012 | DATE - 12/12/94 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
TRAFFIC SYSTEMS CENTER

FLASHER DETAIL SHEET

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

| | | | | |
|---|---------|--------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | | | 404 | 358 |
| CONTRACT NO. | | | | |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | |