

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	DRAINAGE
				0005	0043
				URBAN	URBAN
20200100	EARTH EXCAVATION	CU YD	211.5		211.5
20400800	FURNISHED EXCAVATION	CU YD	143.4		143.4
20800150	TRENCH BACKFILL	CU YD	314		314
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,600	4,600	
21400100	GRADING AND SHAPING DITCHES	FOOT	1,040		1,040
25000400	NITROGEN FERTILIZER NUTRIENT	POUNDS	86	86	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUNDS	86	86	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUNDS	86	86	
25200110	SODDING, SALT TOLERANT	SQ YD	4,600	4,600	
25200200	SUPPLEMENTAL WATERING	UNIT	230	230	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	95		95
28000305	TEMPORARY DITCH CHECKS	FOOT	100		100
28000400	PERIMETER EROSION CONTROL BARRIER	FOOT	2,540		2,540
28000510	INLET FILTERS	EACH	11		11
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	4,600		4,600

URBAN

• SPECIALTY ITEMS

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: spornel
 CLIENT: 2/8/2013 14:53:40
 DATE PLOTTED: 860005601-sum.dwg
 FILE NAME: pof.dwg
 PLOT USER: s.pornel
 PLOT SCALE: 1/8"=1'-0"



USER NAME = spornel	DESIGNED - CMH	REVISED -
PLOT SCALE = N.T.S.	DRAWN - SMP	REVISED -
PLOT DATE = 2/8/2013	CHECKED - TEH	REVISED -
	DATE - 2/8/13	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
127TH STREET (RIDGELAND AVE. TO IL RTE. 83)			
SCALE: N.T.S.	SHEET NO. 1 OF 5 SHEETS	STA. NA	TO STA. NA

F.A. RTE. 1587	SECTION 3034-R5-S	COUNTY COOK	TOTAL SHEETS 48	SHEET NO. 3
CONTRACT NO. 60L82			ILLINOIS FED. AID PROJECT	