

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	DRAINAGE
			URBAN		
			0005	0043	
			URBAN	URBAN	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	332	332	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18	
40600300	AGGREGATE (PRIME COAT)	TON	95	95	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	943	943	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	355	355	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	285	285	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	50	50	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,031	2,031	
42001300	PROTECTIVE COAT	SO YD	56	56	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	23,606	23,606	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	426	426	
44002213	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/4"	SO YD	1,520	1,520	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	203	203	

\* SPECIALTY ITEMS

COMPANY NAME: HRGreen  
 PROJECT CONTACT: HRGreen.com  
 CLIENT: HRGreen.com  
 DATE PLOTTED: 2/8/2013 1:46:20 AM  
 FILE NAME: 8600016401-sum.dgn  
 PLOT DRIVER: pctclp  
 PER TABLE: 8600016401-sum.tbl



USER NAME: c_sporral	DESIGNED - CMH	REVISED -
PLOT SCALE = N.T.S.	DRAWN - SMP	REVISED -
PLOT DATE = 2/8/2013	CHECKED - TEH	REVISED -
	DATE - 2/8/13	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
127TH STREET (RIDGELAND AVE. TO IL RTE. 83)			
SCALE: N.T.S.	SHEET NO. 2 OF 5 SHEETS	STA. NA	TO STA. NA

F.A. RTE. 1587	SECTION 3034-R5-S	COUNTY COOK	TOTAL SHEETS 48	SHEET NO. 4
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT		
		CONTRACT NO. 60L82		