

127TH STREET EARTHWORK			
STATION	20200100	20400800	EARTHWORK BALANCE WASTE (+) OR
	EARTH EXCAVATION	FURNISHED EXCAVATION	
120+00.00	0.0	0.0	0.0
120+50.00	10.2	2.9	7.3
121+00.00	16.6	3.6	13.0
121+50.00	13.9	0.8	13.1
122+00.00	20.2	0.2	20.0
122+17.20	4.4	0.1	4.3
122+31.80	0.2	3.3	-3.1
122+50.00	0.2	4.2	-4.1
123+00.00	8.2	0.6	7.6
123+42.12	6.9	15.4	-8.5
123+50.00	0.3	2.9	-2.6
123+70.31	0.8	0.0	0.8
124+00.00	1.8	1.6	0.2
124+50.00	11.5	2.8	8.7
125+00.00	16.7	0.3	16.4
125+14.75	4.6	0.2	4.5
125+50.00	5.2	0.2	5.0
126+00.00	1.4	1.4	0.0
126+50.00	4.3	3.6	0.6
126+67.83	2.2	1.1	1.1
127+00.00	4.2	1.7	2.4
127+45.64	7.2	4.1	3.0
127+50.00	0.9	0.5	0.4
128+00.00	12.1	3.2	8.9
128+50.00	11.0	0.3	10.7
128+71.21	1.8	0.0	1.8
129+00.00	1.2	1.0	0.2
129+09.03	0.9	0.5	0.4
129+39.10	3.9	1.7	2.2
129+50.00	1.8	0.5	1.3
130+00.00	7.3	1.8	5.6
130+27.77	1.5	0.6	0.9
130+50.00	0.9	2.7	-1.8
131+00.00	2.0	6.0	-4.0
131+50.00	2.5	5.6	-3.1
131+75.57	2.4	5.5	-3.2
132+00.00	2.1	6.2	-4.2
132+50.00	4.4	16.7	-12.2
133+00.00	4.4	20.2	-15.7
133+26.59	1.6	13.0	-11.4
133+50.00	2.9	6.3	-3.4
133+96.73	4.9	0.0	4.9
TOTALS	211.5	143.4	68.1
	CU YD	CU YD	CU YD

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: Illinois Professional Design Firm
 DATE PLOTTED: 2/8/2013 14:53:44
 FILE NAME: 46100196.01-sch-01.dgn
 PLOT DRIVER: pdfcut
 PEN TABLE: standard-trans.tbl



USER NAME = spenel	DESIGNED - CMH	REVISED -
PLOT SCALE = N.T.S.	DRAWN - SMP	REVISED -
PLOT DATE = 2/8/2013	CHECKED - TEH	REVISED -
	DATE - 2/8/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
127TH STREET (RIDGELAND AVE. TO IL RTE. 83)

SCALE: N.T.S. SHEET NO. 1 OF 1 SHEETS STA. BEGIN TO STA. END

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1587	3034-RS-S	COOK	48	8
CONTRACT NO.			60L82	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		