

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	29	29				
25200110	SOODING, SALT TOLERANT	SO YD	29	29				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	21	21				
40600300	AGGREGATE (PRIME COAT)	TON	102	102				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	39	39				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	1050	1050				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	331	331				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	135	135				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2500	2500				
42001300	PROTECTIVE COAT	SO YD	60	60				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	12	12				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 100% STATE				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	23966	23966				
44000600	SIDEWALK REMOVAL	SO FT	12	12				
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	590	590				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	461	461				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	20	20				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	29	29				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	5	5				
60406000	FRAMES AND LIDS, TYPE I, OPEN LID	EACH	3	3				
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	4	4				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2850	2850				

FILE NAME =	USER NAME = kthredmm	DESIGNED -	REVISED -
c:\pwwork\p10041011\redmm\0230640\000001.ste		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**US ROUTE 14 (LUTHER LANE TO E0 GREENWOOD AVE.)
SUMMARY OF QUANTITIES**

F.A. RTE. 1324	SECTION 2010-094-RS	COUNTY COOK	TOTAL SHEETS 22	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60L93	

Rev 4-10-13