

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY STATE 0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY STATE 0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	100	100					44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	737	737				
25200110	SODDING, SALT TOLERANT	SO YD	100	100					48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	951	951				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	65	65					60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	6	6				
40600300	AGGREGATE (PRIME COAT)	TON	324	324					60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	8	8				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	122	122					60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	3	3				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	3300	3300					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					67100100	MOBILIZATION	L SUM	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	309	309					70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6824	6824					70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
42101300	PROTECTIVE COAT	SQ YD	200	200					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	81244	81244					70300100	SHORT TERM PAVEMENT MARKING	FOOT	19323	19323				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	314	314					70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	472	472				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	39	39					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	61179	61179				

URBAN
100%
STATE

URBAN
100%
STATE

13

FILE NAME: c:\pwr\work\pilot\gulltown\pilot235170-00641-11-11.dwg	USER NAME: gulltownfp	DESIGNED: -	REVISED: -
PLOT SCALE: 1/8" = 1'-0"	CHECKED: -	DATE: -	REVISED: -
PLOT DATE: 12/24/2002			

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 7 (SOUTHWEST HWY)
SUMMARY OF QUANTITIES**

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.U. RTE. 3578	SECTION 3178 (B&C) RS-1	COUNTY COOK	TOTAL SHEETS 34	SHEET NO. 3
--------	---------------------	--------------	------------------	-------------------------	-------------	-----------------	-------------

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3578	3178 (B&C) RS-1	COOK	34	3
CONTRACT NO. 60L97				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				