

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY					
				0005					
<del>40600200</del>	<del>BITUMINOUS MATERIALS (PRIME COAT)</del>	<del>TON</del>	<del>51</del>	<del>51</del>					
<del>40600300</del>	<del>AGGREGATE (PRIME COAT)</del>	<del>TON</del>	<del>230</del>	<del>230</del>					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	35	35					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4875	4875					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	691	691					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	283	283					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	11245	11245					
42001300	PROTECTIVE COAT	SO YD	315	315					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	114740	114740					
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SO YD	1010	1010					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	659	659					

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY					
				0005					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	172	172					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	81	81					
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	40	40					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	42938	42938					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	1841	1841					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	56630	56630					

Rev. 4-11-13

FILE NAME *	USER NAME *	DESIGNED -	REVISED -
CLIP.../.../...	...	DRAWN -	REVISED -
PLOT SCALE *		CHECKED -	REVISED -
PLOT DATE *		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	2010-109-R5	COOK	32	3
CONTRACT NO. 60M36				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				