

URBAN

URBAN

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	ROADWAY					
				0005					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	8400	8400					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	550	550					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	450	450					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1350	1350					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	14313	14313					
#78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1841	1841					
#78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	56630	56630					
#78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	8400	8400					
#78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	550	550					
#78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	450	450					
#78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1350	1350					

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	ROADWAY					
				0005					
#78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2711	2711					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1627	1627					
88600600	DETECTOR LOOP REPLACEMENT	FOOT	5045	5045					
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	50	50					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	900	900					
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
	X4060120 NON-TRACKING BITUMINOUS MATERIAL (PRIME COAT)	POUND	77,450	77,450					
	* SPECIALITY ITEMS								

X4060120 NON-TRACKING BITUMINOUS MATERIAL (PRIME COAT) POUND 77,450 77,450

Rev. 4-22-13

Rev. 4-11-13

FILE NAME	USER NAME	DESIGNED	REVISED
DATE	CHECKED	DRAWN	REVISED
PLOT SCALE	DATE	CHECKED	REVISED
PLOT DATE	DATE	CHECKED	REVISED

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	2010-109-R5	COOK	32	3A
FED. ROAD DIST. NO. 1			ILLINOIS FED. AID PROJECT	

SCALE: SHEET NO. OF SHEETS STA. TO STA.