


•=SPECIALTY ITEM, **=80% FED, 10% STATE, 10% OP
 OP=VILLAGE OF ORLAND PARK, STA=STATE
 OFD=ORLAND FIRE PROTECTION DISTRICT

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 158TH	TRAFFIC SIGNALS 156TH	TRAFFIC SIGNALS 151ST	TRAFFIC SIGNALS 153RD	TRAFFIC SIGNALS 149TH	TRAFFIC SIGNALS 147TH	TRAFFIC SIGNALS 144TH	TRAFFIC SIGNALS RAV/151ST	INTERCONNECT	WATER MAIN/SAN SEWER	RETAINING WALLS	NEW SIDEWALK/BIKE PATH	EVP	
				80% FED 20% STA 0003	100% OP 0021	100% OP 0021	** 0021	100% OP 0021	** 0021	** 0021	** 0021	** 0021	** 0021	** 0021	100% OP 0021	80% FED 20% STA 0021	100% OP 0043	80% FED 20% STA 0040	80% FED 20% OP 0028
50300285	FORM LINER TEXTURED SURFACE	50 FT	23,002																
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	139,650																
50901750	PARAPET RAILING	FOOT	863																
50900105	ALUMINUM RAILING, TYPE L	FOOT	368																
50901760	PIPE HANDRAIL	FOOT	12																
51200957	FURNISHING METAL PILE SHELLS 12" X 0.250"	FOOT	9718																
51201600	FURNISHING STEEL PILES HP12X53	FOOT	2150																
51202305	DRIVING PILES	FOOT	9718																
51500100	NAME PLATES	EACH	2																
51203600	TEST PILE STEEL HP12X53	EACH	4																
51203200	TEST PILE METAL SHELLS	EACH	2																
51204650	PILE SHOES	EACH	108																
54010900	PRECAST CONCRETE BOX CULVERTS 9' X 0'	FOOT	21																
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1															
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1															
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	137	137															
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	7844	7844															
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	588	588															
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	750	750															

Rev. 4-16-13



FILE NAME * D:\60M61-SHT-500.dgn	USER NAME * Frank.Stallone	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE - 02/07/2013	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 5 OF 22 SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 103R-4	COUNTY COOK	TOTAL SHEETS 877	SHEET NO. 9
CONTRACT NO. 60M61				
ILLINOIS FED. AID PROJECT				