


=SPECIALTY ITEM, *=80% FED, 10% STATE, 10% OP
 OP=VILLAGE OF ORLAND PARK, STA=STATE
 OFD=ORLAND FIRE PROTECTION DISTRICT

URBAN

CONSTRUCTION CODE

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | ROADWAY | LIGHTING | TRAFFIC SIGNALS 158TH | TRAFFIC SIGNALS 156TH | TRAFFIC SIGNALS 153RD | TRAFFIC SIGNALS 151ST | TRAFFIC SIGNALS 149TH | TRAFFIC SIGNALS 147TH | TRAFFIC SIGNALS 144TH | TRAFFIC SIGNALS RAV/151ST | INTERCONNECT | WATER MAIN/SAN SEWER | RETAINING WALLS | NEW SIDEWALK/BIKE PATH | EVP |
|----------|--|--------|----------------|----------------------|--------------|-----------------------|-----------------------|-----------------------|-----------------------|-----------------------|-----------------------|-----------------------|---------------------------|--------------|----------------------|----------------------|------------------------|----------------------|
| | | | | 80% FED 20% STA 0003 | 100% OP 0021 | 100% OP 0021 | ** 0021 | 100% OP 0021 | ** 0021 | ** 0021 | ** 0021 | ** 0021 | ** 0021 | ** 0021 | 100% OP 0021 | 80% FED 20% STA 0021 | 100% OP 0043 | 80% FED 20% STA 0040 |
| 35101582 | AGGREGATE BASE COURSE, TYPE B 2" | SO YD | 10796 | 10796 | | | | | | | | | | | | | | |
| 35102000 | AGGREGATE BASE COURSE, TYPE B 8" | SO YD | 2348 | 2348 | | | | | | | | | | | | | | |
| 35501316 | HOT-MIX ASPHALT BASE COURSE, 8" | SO YD | 1415 | 1415 | | | | | | | | | | | | | | |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 2278 | 2278 | | | | | | | | | | | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 | 2 | | | | | | | | | | | | | | |
| 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 296 | 296 | | | | | | | | | | | | | | |
| 40603335 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 | TON | 2387 | 2387 | | | | | | | | | | | | | | |
| 40701931 | HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12 1/2" | SO YD | 22146 | 22146 | | | | | | | | | | | | | | |
| 42000501 | PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) | SO YD | 83385 | 83385 | | | | | | | | | | | | | | |
| 42001300 | PROTECTIVE COAT | SO YD | 127,756 | 127,663 | | | | | | | | | | | | 93 | | |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SO YD | 3385 | 3385 | | | | | | | | | | | | | | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SO FT | 28545 | 21710 | | | | | | | | | | | | | 6835 | |
| 42400800 | DETECTABLE WARNINGS | SO FT | 2806 | 2720 | | | | | | | | | | | | | 86 | |
| 44000100 | PAVEMENT REMOVAL | SO YD | 141121 | 141121 | | | | | | | | | | | | | | |



| | | | |
|-------------------------------------|-------------------------------|-------------------|-----------|
| FILE NAME * D:\60M61-SHT-500.dgn | USER NAME * Frank.Stallone | DESIGNED - | REVISED - |
| SHT_PLAN | PLOT SCALE * 100.0045 ' / in. | DRAWN - | REVISED - |
| | PLOT DATE * 2/8/2013 | CHECKED - | REVISED - |
| | | DATE - 02/07/2013 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 3 OF 22 SHEETS STA. TO STA.

| | | | | |
|--------------------|-------------------|----------------|---------------------------|----------------|
| F.A.P. RTE. 330 | SECTION 103R-4 | COUNTY COOK | TOTAL SHEETS 877 | SHEET NO. 7 |
| CONTRACT NO. 60M61 | | | ILLINOIS FED. AID PROJECT | |