


•=SPECIALTY ITEM, \*\*=80% FED, 10% STATE, 10% OP  
 OP=VILLAGE OF ORLAND PARK, STA=STATE  
 OFD=ORLAND FIRE PROTECTION DISTRICT

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 158TH	TRAFFIC SIGNALS 156TH	TRAFFIC SIGNALS 153RD	TRAFFIC SIGNALS 151ST	TRAFFIC SIGNALS 149TH	TRAFFIC SIGNALS 147TH	TRAFFIC SIGNALS 144TH	TRAFFIC SIGNALS RAV/151ST	INTERCONNECT	WATER MAIN/SAN SEWER	RETAINING WALLS	NEW SIDEWALK/BIKE PATH	EVP
				80% FED 20% STA 0003	100% OP 0021	100% OP 0021	** 0021	100% OP 0021	** 0021	** 0021	** 0021	** 0021	** 0021	100% OP 0021	80% FED 20% STA 0021	100% OP 0043	80% FED 20% STA 0040	80% FED 20% OP 0028
60256940	MANHOLES TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1														
60260100	INLETS TO BE ADJUSTED	EACH	4	4														
60262700	INLETS TO BE RECONSTRUCTED	EACH	4	4														
60261530	INLETS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	10	10														
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1														
<del>60261540</del>	<del>INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE</del>	<del>EACH</del>	<del>10</del>	<del>10</del>														
60403700	LIDS, TYPE 1, OPEN LID	EACH	20	20														
60403800	LIDS, TYPE 1, CLOSED LID	EACH	40	40														
60404940	FRAMES AND GRATES, TYPE 23	EACH	65	65														
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5														
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10														
60500040	REMOVING MANHOLES	EACH	38	38														
60500050	REMOVING CATCH BASINS	EACH	101	101														
60500060	REMOVING INLETS	EACH	14	14														
60500405	FILLING VALVE VAULTS	EACH	13												13			
60600605	CONCRETE CURB, TYPE B	FOOT	14,082	5066	9016													



FILE NAME DIG08G1-SHT-500.dgn	USER NAME Frank.Stallone	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
SHT_PLAN	PLOT DATE 2/8/2013	DATE 02/07/2013	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
SCALE:	SHEET 9 OF 22 SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 103R-4	COUNTY COOK	TOTAL SHEETS 877	SHEET NO. 13
CONTRACT NO. 60M61			ILLINOIS FED. AID PROJECT	