

\*=SPECIALTY ITEM, \*\*=80% FED, 10% STATE, 10% OP  
 OP=VILLAGE OF ORLAND PARK, STA=STATE  
 OFD=ORLAND FIRE PROTECTION DISTRICT

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 158TH	TRAFFIC SIGNALS 156TH	TRAFFIC SIGNALS 154TH	TRAFFIC SIGNALS 153RD	TRAFFIC SIGNALS 151ST	TRAFFIC SIGNALS 149TH	TRAFFIC SIGNALS 147TH	TRAFFIC SIGNALS 144TH	TRAFFIC SIGNALS RAV/151ST	INTERCONNECT	WATER MAIN/SAN SEWER	RETAINING WALLS	NEW SIDEWALK/BIKE PATH	EVP
				80% FED 20% STA	100% OP	100% OP	**	100% OP	**	**	**	**	**	**	100% OP	80% FED 20% STA	100% OP	80% FED 20% STA	80% FED 20% OP
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	400	400															
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	144	144															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	20660	20660															
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1500	1500															
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1225	1225															
70600255	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW) TEST LEVEL 2 <i>FULLY</i>	EACH	6	6															
70600322	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE, NARROW) TEST LEVEL 2 <i>FULLY</i>	EACH	4	4															
* 72000100	SIGN PANEL - TYPE 1	SO FT	1130	830			60	60	30	30	30	60	30						
* 72000200	SIGN PANEL - TYPE 2	SQ FT	135	135															
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	112	112															
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	5	5															
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	27	27															
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	88	88															
<del>* 72900100</del>	<del>METAL POST - TYPE A</del>	<del>FOOT</del>	<del>209</del>	<del>209</del>															
* 73000100	WOOD SIGN SUPPORT	FOOT	216	216															
* 72900200	METAL POST - TYPE B	FOOT	1195	1195															
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	8	8															
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12243	12243															
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	744	744															
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2644	2644															

URS  
 100 S. WACKER DR.  
 SUITE 500  
 CHICAGO, IL 60606  
 TEL 312-535-0000  
 FAX 312-535-4988

FILE NAME * D168M61-SHT-500.dgn	USER NAME * Frank.Stallone	DESIGNED -	REVISOR -
SHT.PLAN	PLOT SCALE * 1/8"=1'-0"	DRAWN -	REVISIONS -
	PLOT DATE * 2/8/2013	CHECKED -	DATE - 02/07/2013
		DATE -	REVISIONS -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 SCALE: SHEET 11 OF 22 SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 103R-4	COUNTY COOK	TOTAL SHEETS 877	SHEET NO. 15
CONTRACT NO. 60M61				
ILLINOIS FED. AID PROJECT				