


=SPECIALTY ITEM, *=80% FED, 10% STATE, 10% OP
 OP=VILLAGE OF ORLAND PARK, STA=STATE
 OFD=ORLAND FIRE PROTECTION DISTRICT

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 158TH	TRAFFIC SIGNALS 156TH	TRAFFIC SIGNALS 154TH	TRAFFIC SIGNALS 153RD	TRAFFIC SIGNALS 151ST	TRAFFIC SIGNALS 149TH	TRAFFIC SIGNALS 147TH	TRAFFIC SIGNALS 144TH	TRAFFIC SIGNALS RAV/151ST	INTERCONNECT	WATER MAIN/SAN SEWER	RETAINING WALLS	NEW SIDEWALK/BIKE PATH	EVP
				80% FED 20% STA 0003	100% OP 0021	100% OP 0021	** 0021	100% OP 0021	** 0021	** 0021	** 0021	** 0021	** 0021	** 0021	** 0021	100% OP 0021	80% FED 20% STA 0021	100% OP 0043	80% FED 20% STA 0040
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1206	1206															
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	120	120															
78300100	PAVEMENT MARKING REMOVAL	SO FT	9120	9120															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	500	500															
80400100	ELECTRIC SERVICE INSTALLATION	EACH	6	6															
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1															
80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	5			1			1	1	1	1	1						
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2					1	1										
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	14,503			262	843	1894	960	863	799	857	855	255	6915				
* 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	205				37	30	4	65	8	53	8						
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	150				34	43		25	9	25	14						
81028230	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3 1/2" DIA.	FOOT	205				3	7	80	17	31	37	30						
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	15,388	8197			568	568	621	575	596	512	511			3240			
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	10,696	1313												9383			
81200260	CONDUIT EMBEDDED IN STRUCTURE, 3 1/2" DIA., PVC	FOOT	605	605															



FILE NAME * D:\6061-SHT-500.dgn	USER NAME * Frank.Stallone	DESIGNED -	REVISED -
SHT_PLAN	PLOT SCALE * 1/8"=1'-0"	CHECKED -	REVISED -
	PLOT DATE * 2/8/2013	DATE - 02/07/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 13 OF 22 SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 103R-4	COUNTY COOK	TOTAL SHEETS 877	SHEET NO. 17
CONTRACT NO. 60M61			ILLINOIS FED. AID PROJECT	