

==SPECIALTY ITEM, **=80% FED, 10% STATE, 10% OP
 OP=VILLAGE OF ORLAND PARK, STA=STATE
 OFD=ORLAND FIRE PROTECTION DISTRICT

URBAN

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 158TH	TRAFFIC SIGNALS 156TH	TRAFFIC SIGNALS 154TH	TRAFFIC SIGNALS 153RD	TRAFFIC SIGNALS 151ST	TRAFFIC SIGNALS 149TH	TRAFFIC SIGNALS 147TH	TRAFFIC SIGNALS 144TH	TRAFFIC SIGNALS RAV/151ST	INTERCONNECT	WATER MAIN/SAN SEWER	RETAINING WALLS	NEW SIDEWALK/BIKE PATH	EVP
				80% FED 20% STA 0003	100% OP 0021	100% OP 0021	** 0021	100% OP 0021	** 0021	** 0021	** 0021	** 0021	** 0021	** 0021	** 0021	100% OP 0021	80% FED 20% STA 0021	100% OP 0043	80% FED 20% STA 0040
81400100	HANDHOLE	EACH	102		20	1	3	7	4	4	4	4	4	1	8	42			
81400200	HEAVY-DUTY HANDHOLE	EACH	32				4	4	4	4	4	4	4			4			
81400300	DOUBLE HANDHOLE	EACH	16				3	3	2	2	2	2	2						
81603051	UNIT DUCT, 600V, 3-1/C NO. 6, 1/C NO. 8 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	24067		24067														
81603060	UNIT DUCT, 600V, 3-1/C NO. 8 1/C NO. 10 GROUND (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	535		535														
81603063	UNIT DUCT, 600V, 4-1/C NO. 10, 1/C NO. 10 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2654		2654														
81603081	UNIT DUCT, 600V, 3-1/C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	24077		24077														
81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	11057		11057														
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	24		24														
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	94		94														
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	1070		1070														
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	41		41														
84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	98		98														
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	44		44														
84200804	REMOVAL OF POLE FOUNDATION	EACH	64		64														

URS
 100 S. WACKER DR.
 SUITE 500
 CHICAGO, IL 60606
 TEL 312/998-4000
 FAX 312/998-4088

FILE NAME DIGM61-SHT-500.dgn	USER NAME Frank.Scallone	DESIGNED - DRAWN -	REVISED - REVISED -
SHT_PLAN	PLOT SCALE 1/8"=1'-0"	CHECKED - DATE - 02/07/2013	REVISED - REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
SCALE:	SHEET 14 OF 22 SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 103R-4	COUNTY COOK	TOTAL SHEETS 877	SHEET NO. 18
CONTRACT NO. 60M61				
ILLINOIS FED. AID PROJECT				