

•=SPECIALTY ITEM, ••=80% FED, 10% STATE, 10% OP
 OP=VILLAGE OF ORLAND PARK, STA=STATE
 OFD=ORLAND FIRE PROTECTION DISTRICT

URBAN

CONSTRUCTION CODE

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | ROADWAY | LIGHTING | TRAFFIC SIGNALS 158TH | TRAFFIC SIGNALS 156TH | TRAFFIC SIGNALS DARWIN | TRAFFIC SIGNALS 153RD | TRAFFIC SIGNALS 151ST | TRAFFIC SIGNALS 149TH | TRAFFIC SIGNALS 147TH | TRAFFIC SIGNALS 144TH | TRAFFIC SIGNALS RAV/151ST | INTERCONNECT | WATER MAIN/SAN SEWER | RETAINING WALLS | NEW SIDEWALK/BIKE PATH | EVP | |
|------------|---|-------|----------------|----------------------------|-----------------|-----------------------|-----------------------|------------------------|-----------------------|-----------------------|-----------------------|-----------------------|-----------------------|---------------------------|--------------|----------------------|-----------------|----------------------------|-----------------|----------------------------|
| | | | | 80% FED 20% STA 0003 | 100% OP 0021 | 100% OP 0021 | •• 0021 | 100% OP 0021 | •• 0021 | •• 0021 | •• 0021 | •• 0021 | •• 0021 | •• 0021 | •• 0021 | •• 0021 | 100% OP 0021 | 80% FED 20% STA 0021 | 100% OP 0043 | 80% FED 20% STA 0040 |
| * X0326498 | GFCI 20 AMP DUPLEX RECEPTACLE | EACH | 61 | | 61 | | | | | | | | | | | | | | | |
| * X0327004 | TEMPORARY WOOD POLE, 60 FT., CLASS 4 | EACH | 8 | | 8 | | | | | | | | | | | | | | | |
| X4021000 | TEMPORARY ACCESS (PRIVATE ENTRANCE) | EACH | 1 | 1 | | | | | | | | | | | | | | | | |
| X4022000 | TEMPORARY ACCESS (COMMERCIAL ENTRANCE) | EACH | 87 | 87 | | | | | | | | | | | | | | | | |
| X4023000 | TEMPORARY ACCESS (ROAD) | EACH | 7 | 7 | | | | | | | | | | | | | | | | |
| X4024000 | TEMPORARY ACCESS (FIELD ENTRANCE) | EACH | 1 | 1 | | | | | | | | | | | | | | | | |
| X4024100 | TEMPORARY ACCESS (WINTERIZE) | SO YD | 7951 | 7951 | | | | | | | | | | | | | | | | |
| X4200110 | HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) | SO YD | 21109 | 21109 | | | | | | | | | | | | | | | | |
| X4402805 | ISLAND REMOVAL | SO FT | 1601 | 1601 | | | | | | | | | | | | | | | | |
| X4404000 | PARKING LOT PAVEMENT REMOVAL | SO YD | 4873 | 4873 | | | | | | | | | | | | | | | | |
| X5121800 | PERMANENT STEEL SHEET PILING | SO FT | 35,762 | | | | | | | | | | | | | | | 35,762 | | |
| X550A562 | TEMPORARY STORM SEWERS, CLASS A, TYPE 2 12" | FOOT | 441 | 441 | | | | | | | | | | | | | | | | |
| X5860110 | GRANULAR BACKFILL FOR STRUCTURES | CU YD | 629 | | | | | | | | | | | | | | | | | 629 |
| X6020095 | MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE | EACH | 1 | 1 | | | | | | | | | | | | | | | | |
| X6640304 | CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED | FOOT | 120 | 120 | | | | | | | | | | | | | | | | |
| X6021193 | TEMPORARY CATCH BASINS | EACH | 41 | 41 | | | | | | | | | | | | | | | | |

* Specialty Items

URS
 100 S. WACKER DR.
 SUITE 500
 CHICAGO, IL 60606
 TEL: 312-939-1000
 FAX: 312-939-4198

| | | | |
|-----------------------------------|-----------------------------|-------------------|-----------|
| FILE NAME D:\60M61-SHT-500.dgn | USER NAME Frank.Stallone | DESIGNED - | REVISED - |
| SHT_PLAN | PLOT SCALE = 100.0045' / 1" | DRAWN - | REVISED - |
| | PLOT DATE = 2/8/2013 | CHECKED - | REVISED - |
| | | DATE = 02/07/2013 | REVISED - |

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

| | |
|-----------------------|------------------------------------|
| SUMMARY OF QUANTITIES | |
| SCALE: | SHEET 19 OF 22 SHEETS STA. TO STA. |

| | | | | |
|-----------------------------|-------------------|----------------|---------------------|-----------------------|
| F.A.P. RFE. 330 | SECTION 103R-4 | COUNTY COOK | TOTAL SHEETS 877 | TOTAL SHEET NO. 23 |
| CONTRACT NO. 60M61 | | | | |
| [ILLINOIS] FED. AID PROJECT | | | | |

Rev.