


STORM SEWER REMOVAL 12"
 STA. 264+76.5 TO 264+75.2 - 67' (TBF=22.3 CU YD)
 STA. 264+75.2 TO 264+75.3 - 1' (TBF=0.8 CU YD)
 STA. 267+34.1 TO 268+03.6 - 66' (TBF=50.7 CU YD)
 STA. 267+56.5 TO 268+24.3 - 64' (TBF=10.1 CU YD)
 STA. 268+03.3 TO 268+03.6 - 8' (TBF=9.6 CU YD)
 STA. 268+12.4 TO 268+24.3 - 10' (TBF=8.6 CU YD)
 STA. 268+10.6 TO 268+03.6 - 33' (TBF=21.3 CU YD)
 STA. 268+03.6 TO 268+91.2 - 83' (TBF=120.1 CU YD)
 STA. 269+09.6 TO 270+08.8 - 97' (TBF=15.4 CU YD)
 STA. 269+25.3 TO 270+07.7 - 80' (TBF=12.7 CU YD)

REMOVING INLETS
 264+75.21, 34.8 LT
 267+56.40, 36.9 LT
 268+10.55, 1.0 RT
 268+3.32, 44.2 RT
 269+9.57, 39.4 LT
 269+25.25, 47.6 RT

REMOVING MANHOLES
 264+76.54, 35.2 RT
 267+34.14, 45.0 RT
 268+03.58, 33.0 RT

REMOVING CATCH BASINS
 268+12.36, 31.36 LT



SEE DRAWING DU-15
 MATCH LINE STA. 264+00.00

MATCH LINE STA. 270+00.00
 SEE DRAWING DU-17

NOTES:
 1. SEE DRAWING DN-01 FOR DRAINAGE LEGEND AND NOTES.
 2. SEE DRAWINGS DS-01 THROUGH DS-09 FOR STRUCTURE AND PIPE INFORMATION.

FILE NAME = D160M61-SHT-DRAINEX16.dgn	USER NAME = Anthony.Plutz	DESIGNED - EJD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EXISTING DRAINAGE PLAN - US 55 (LAGRANGE ROAD)			F.A.P. R.T.E. = 330	SECTION = 103R-4	COUNTY = COOK	TOTAL SHEETS = 877	SHEET NO. = 174
	PLOT SCALE = 48.0000' / in.	CHECKED - JWM	REVISED -					DU-16		CONTRACT NO. 60M61		
SHT.PLAN	PLOT DATE = 3/14/2013	DATE = 03/13/2013	REVISED -	SCALE: 1"=20' SHEET 16 OF 17 SHEETS STA. 264+00.00 TO STA. 270+00.00			ILLINOIS FED. AID PROJECT					