

STRUCTURE SCHEDULE

Drawing	STR. NO.	STA.	OFFSET	STRUCTURE	COVER	TEMP. RIM ELEV CONTRACT 60M61	FINAL RIM ELEV. CONTRACT 60M61	N	E	S	W
DU-56	EX70E	179+32.7	28.7' LT	EX MH			711.89	706.44(NW) 12"	706.44(E) 12"		
	71E	179+49.0	23.0' RT	IN TA 2	T24 F&G		711.27		706.77(E) 12"		
	72E	180+10.0	23.8' RT	IN TA 2	T24 F&G		711.28				706.78(W) 12"
	73E	179+79.5	23.0' RT	CB TA 4	T24 F&G		711.20	706.4(N) 12"	706.5(E) 12"		706.49(W) 12"
	74E	179+49.5	19.0' LT	IN TA 2	T24 F&G		711.35		706.85(E) 12"		
	75E	180+10.0	18.5' LT	IN TA 2	T24 F&G		711.35				706.85(W) 12"
	76E	179+79.5	19.0' LT	CB TA 4	T24 F&G		711.28	706.57(N) 12"	706.57(E) 12"	705.98(S) 12"	706.57(W) 12"
	77E	179+79.5	28.4' LT	MH TA 4	T1F CL		711.64		705.97(E) 12"	706.5(S) 12"	706.01(W) 12"
	78E	180+85.3	27.7' LT	MH TA 4/R-PLT	T1F CL		712.28	705.03(N) 12"	704.88(E) 12"		704.98(W) 18"

PIPE SCHEDULE

SHEET	PIPE NO.	STR. NO. FROM	STR. NO. TO	DESCRIPTION	IN DIA.	FT LEN	SLOPE	CU YD TBF
DU-90	34W	34W	35W	SS, CL A, TY 2	12	87.6	1.02%	14.3
	32W	32W	36W	SS, CL A, TY 2	12	24.25	1.02%	6.9
	28E	28E	29E	SS, SS, WMR Y 2	12	28.0	1.05%	9.0
	29E	29E	30E	SS, CL A, TY 2	12	26.0	1.06%	15.27
	35E	35E	36E	SS, CL A, TY 2	12	27.5	1.02%	5.3
	36E	36E	33E	SS, CL A, TY 2	12	5.0	4.50%	0.2
	33E	33E	EX34E	SS, CL A, TY 3	15	47.1	0.51%	85.2
	38W	38W	40W	SS, WMR	12	27.3	1.03%	5.9
	39W	39W	40W	SS, CL A, TY 2	12	26.9	1.04%	5.2
	40W	40W	42W	SS, WMR	15	66.8	1.06%	17.3
	41W	41W	42W	SS, CL A, TY 1	12	26.8	1.01%	3.5
	42W	42W	43W	SS, WMR	15	4.0	2.00%	1.4
	EX43W	43W	45W	EX PIPE	24	26.3	0.72%	0.0
	44W	44W	45W	SS, CL A, TY 2	12	7.1	0.85%	2.7
DU-50	20E	20E	22E	SS, CL A, TY 2	12	54.3	1.03%	12.8
	21E	21E	22E	SS, CL A, TY 2	12	3.2	1.87%	0.7
	23E	24E	25E	SS, CL A, TY 2	12	3.5	1.43%	0.8
	24E	23E	25E	SS, CL A, TY 2	12	54.0	1.06%	12.7
	27E	27E	29E	SS, CL A, TY 2	12	26.5	1.06%	5.1
	30E	30E	32E	SS, CL A, TY 2	12	26.5	1.02%	4.0
DU-51	50W	50W	EX PIPE	SS, CL A, TY 1	12	7.0	0.14%	0.9
	51W	51W	53W	SS, CL A, TY 1	12	45.0	0.51%	5.9
	52W	52W	53W	SS, CL A, TY 1	12	21.3	0.52%	2.8
	53W	53W	50W	SS, CL A, TY 1	12	2.2	0.45%	0.3
DU-52	40E	40E	42E	SS, CL A, TY 2	12	40.0	1.05%	10.3
	41E	41E	42E	SS, CL A, TY 2	12	19.0	1.11%	4.5
	42E	42E	45E	SS, CL A, TY 2	12	222.0	2.55%	29.3
	43E	43E	45E	SS, CL A, TY 2	12	40.0	1.05%	10.3
	44E	44E	45E	SS, CL A, TY 2	12	19.0	1.11%	4.5
	45E	45E	46E	SS, CL A, TY 2	12	45.0	0.76%	11.6
	46E	46E	47E	SS, CL A, TY 2	12	27.7	0.61%	4.2
	47E	47E	EX48E	SS, CL A, TY 1	12	5.2	1.15%	0.7
DU-53	60W	60W	61W	SS, CL A, TY 2	12	47.0	1.06%	10.1
	61W	61W	62W	SS, CL A, TY 2	12	3.8	1.32%	1.0
	62W	62W	EX63W	SS, WMR	12	162.7	1.24%	128.9
DU-54	50E	50E	51E	SS, CL A, TY 2	12	74.0	1.04%	17.5
	51E	51E	52E	SS, CL A, TY 2	12	6.2	1.13%	1.9
	52E	52E	55E	SS, CL A, TY 2	18	195.1	1.06%	74.7
	53E	53E	54E	SS, CL A, TY 2	12	61.6	1.06%	13.2
	54E	54E	55E	SS, CL A, TY 2	12	3.9	1.54%	1.1
	55E	55E	56E	SS, CL A, TY 2	18	57.7	1.06%	39.5
	57E	57E	EX58E	SS, CL A, TY 2	12	3.3	1.52%	0.6
DU-55	70W	70W	71W	SS, CL A, TY 2	12	37.6	1.09%	8.1
	71W	71W	EX72W	SS, CL A, TY 2	12	1.2	1.67%	0.3

* INDICATES STRUCTURE SHALL BE INITIALLY INSTALLED USING A TYPE I FRAME AND CLOSED LID. ULTIMATELY DURING STAGED CONSTRUCTION THE FINAL FRAME AND GRATE WILL BE INSTALLED AND PAID FOR SEPARATELY (REFER TO SUGGESTED SEQUENCE OF DRAINAGE INSTALLATION SHEETS AND STORM SEWER DRAINAGE DETAILS)

FILE NAME = D:\60M61-SHT-Drain Schedules.dgn	USER NAME = Anthony.Plutz	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DRAINAGE SCHEDULE			F.A.P. RFE. 330	SECTION 103R-4	COUNTY COOK	TOTAL SHEETS 877	SHEET NO. 223
SHT.PLAN	PLOT SCALE = 48.000000' / in.	DRAWN -	REVISED -		SCALE:	SHEET 9 OF 9 SHEETS	STA. TO STA.	DS-09		CONTRACT NO. 60M61		
	PLOT DATE = 3/13/2013	CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE - 03/13/2013	REVISED -									