


- NOTES:**
- SEE DRAWING E-1 FOR ELECTRICAL SYMBOL LIST AND ABBREVIATIONS. SEE DRAWING E-2 FOR ELECTRICAL GENERAL NOTES.
  - INDICATES TEMPORARY PAVEMENT INSTALLATION LIMITS. SEE MAINTENANCE OF TRAFFIC DRAWINGS FOR CONSTRUCTION STAGING INFORMATION.
  - EXISTING UNIT DUCTS, CABLE, AND CONDUITS THAT ARE NOT REMOVED AS PART OF THE GENERAL CONTRACT DEMOLITION WORK SHALL BE ABANDONED IN PLACE. IF REMOVAL OF ANY CABLES AND DUCTS IS REQUIRED, PAYMENT FOR THAT WORK SHALL BE INCLUDED IN THE "REMOVAL OF LIGHTING UNIT" PAY ITEM, AND NO SEPARATE PAYMENT WILL BE MADE.
  - CONTRACTOR SHALL COORDINATE WITH MALL MANAGEMENT AND THE VILLAGE OF ORLAND PARK. MAKE SURE REMOVAL OF POLES IS COORDINATED WITH CONSTRUCTION STAGING FOR US45 AND 149TH STREET TO MINIMIZE DOWN TIME FOR THE LIGHT POLES IN CONFLICT WITH CONSTRUCTION.
  - CONTRACTOR SHALL REMOVE 40' POLES FROM LaGRANGE AND RELOCATE THEM TO THE SIDE STREETS, AFTER EXISTING STOCK OF 40' POLES IS DEPLETED, THEN SHORTER POLES CAN BE RELOCATED TO SIDE STREETS AWAY FROM LaGRANGE ROAD, IF NEEDED, AS SHOWN ON THE PLANS.

100 S. WACKER DR.  
 10TH FLOOR  
 CHICAGO, IL 60606  
 TEL (312) 939-1000  
 FAX (312) 939-4198  
**URS**



FILE NAME = D160M61-SHT-E14.dgn	USER NAME = michal_bartusiewicz	DESIGNED - MAE	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>153rd STREET &amp; 149th STREET TEMPORARY LIGHTING AND DEMOLITION PLAN</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
SHT_PLAN	PLOT SCALE = 100.000000' / in.	CHECKED - DAD	REVISED -		SCALE: 1"=50'	SHEET	5 OF 7 SHEETS	STA.	TO STA.	330	103R-4	COOK	877 425
	PLOT DATE = 3/15/2013	DATE - 03/13/2013	REVISED -							<b>E-14</b>			CONTRACT NO. 60M61
ILLINOIS FED. AID PROJECT													

D160M61-SHT-E14.dgn 3/15/2013 2:27:05 PM