

NOTES:

- SEE DRAWING E-1 FOR ELECTRICAL SYMBOL LIST AND ABBREVIATIONS. SEE DRAWING E-2 FOR ELECTRICAL GENERAL NOTES.
- CONTRACTOR MUST ROUTE CONDUIT FROM A LOCATION SPECIFIED BY COMED TO THE PRIMARY SIDE OF THE PROPOSED SERVICE TRANSFORMER. CONDUIT MATERIAL AND SIZE TO BE DETERMINED BY COMED, AND PAID FOR UNDER THE "ELECTRIC UTILITY SERVICE CONNECTION" PAY ITEM. SEPARATE PAYMENT WILL NOT BE MADE.
- SEE DETAIL DRAWING FOR PROPOSED LIGHTING UNIT DETAILS. SEE IDOT STANDARD DRAWING BE-301 FOR PROPOSED LIGHTING UNIT FOUNDATION DETAILS, UNLESS NOTED OTHERWISE.
- SEE DRAWING E-59 FOR PROPOSED RETAINING WALL MOUNTED LIGHTING UNIT INSTALLATION DETAILS.
- CONTRACTOR MUST RUN TEMPORARY AERIAL CABLE TO COMPLETE LIGHTING CIRCUITS A, B, G, AND H. 3-1/C #2 & 1/C #4 GROUND ELECTRIC CABLE ASSEMBLY SHALL BE USED FOR TEMPORARY UNDERGROUND AND VERTICAL RUNS ALONG WOOD POLES AS SHOWN ON DRAWING E-67. THE COST OF THIS WORK SHALL BE INCLUDED IN THE "ELECTRIC CABLE ASSEMBLY IN TRENCH, 600V (EPR-TYPE TC) 3-1/C NO. 2 AND NO. 4 GROUND" AND THE "AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE" PAY ITEMS. SEPARATE PAYMENT WILL NOT BE MADE. RECEPTACLE CIRCUITS SHALL NOT BE ENERGIZED BY TEMPORARY MEANS.
- CONTRACTOR TO FURNISH AND INSTALL (3) 3/2" x 36" RADIUS PVC CONDUIT RACEWAY ELBOWS IN FOUNDATION PER IDOT STANDARD DRAWING BE-301.


100 S. WACKER DR.
 CHICAGO, IL 60606
 TEL (312) 939-1000
 FAX (312) 939-4998
URS

FILE NAME =	USER NAME = michael_bartusiewicz	DESIGNED - MAE	REVISED -
D160M61-SHT-E18.dgn		DRAWN - MAE	REVISED -
	PLOT SCALE = 100.000000' / 1" =	CHECKED - DAD	REVISED -
SHT_PLAN	PLOT DATE = 3/15/2013	DATE - 03/13/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US 45 (LaGRANGE ROAD)
TEMPORARY ROADWAY LIGHTING PLAN - STAGE 1A
 SCALE: 1"=50' SHEET 2 OF 7 SHEETS STA. 195+00.00 TO STA. 225+00.00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	103R-4	COOK	877	429
E-18			CONTRACT NO.	60M61
ILLINOIS FED. AID PROJECT				



D160M61-SHT-E18.dgn 3/15/2013 2:27:09 PM