


SEE DRAWING E-23 FOR CONTINUATION

SEE DRAWING E-23 FOR CONTINUATION

NOTES:

1. SEE DRAWING E-1 FOR ELECTRICAL SYMBOL LIST AND ABBREVIATIONS. SEE DRAWING E-2 FOR ELECTRICAL GENERAL NOTES.
2. CONTRACTOR MUST REINSTALL EXISTING LIGHTING UNIT ON NEW POLE FOUNDATION WITH THE SAME BOLT CIRCLE DIAMETER AS WAS DETERMINED PER NOTE 4 ON DRAWING E-13. SEE IDOT STANDARD DRAWING BE-301 FOR PROPOSED LIGHTING UNIT FOUNDATION DETAILS. FOUNDATION WILL BE PAID FOR UNDER THE "LIGHT POLE FOUNDATION, 24" DIAMETER" PAY ITEM. SEPARATE PAYMENT WILL NOT BE MADE.
3. CONTRACTOR MUST DEENERGIZE THE SERVICE FEED TO BOTH CONTROLLERS RWP-1 AND H-2 DURING THE SAME TIME BEFORE SPLICING UD CONDUCTORS TO APPROPRIATE EXISTING CIRCUIT CABLES WITHIN THE EXISTING HANDHOLE. CONTRACTOR MUST REENERGIZE BOTH CONTROLLERS AS SOON AS THE ELECTRICAL ITEMS ARE INSTALLED AND CONNECTED.
4. SEE DETAIL DRAWING FOR PROPOSED LIGHTING UNIT DETAILS. SEE IDOT STANDARD DRAWING BE-301 FOR PROPOSED LIGHTING UNIT FOUNDATION DETAILS.
5. TRANSITION FROM 3/8" PVC CONDUIT ELBOW TO 3/4" POLYETHYLENE CONDUIT TO ROUTE CONDUCTORS FROM RELOCATED LIGHT POLE FOUNDATION TO EXISTING HOLIDAY TREE LIGHTING RECEPTACLE. PROPOSED RECEPTACLE CIRCUIT CONDUCTORS MUST BE CONNECTED TO EXISTING FUSES WITHIN LIGHT POLE TO BE RELOCATED. THIS WORK WILL BE PAID UNDER THE "REMOVE AND RELOCATE EXISTING LIGHT STANDARD" PAY ITEM. SEPARATE PAYMENT WILL NOT BE MADE.
6. CONTRACTOR TO CONNECT PROPOSED CONDUIT AND WIRING TO EXISTING HOLIDAY TREE LIGHTING RECEPTACLE IN THE SAME MANNER AS EXISTING CONNECTIONS WERE MADE. THIS WORK WILL BE PAID UNDER THE "REMOVE AND RELOCATE EXISTING LIGHT STANDARD" PAY ITEM. SEPARATE PAYMENT WILL NOT BE MADE.



100 S. WACKER DR.
 SUITE 600
 CHICAGO, IL 60606
 TEL (312) 939-1000
 FAX (312) 939-4998
URS

FILE NAME = D:\6061-SHT-E20.dgn	USER NAME = michal_bartusiewicz	DESIGNED - MAE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 45 (LaGRANGE ROAD) TEMPORARY ROADWAY LIGHTING PLAN - STAGE 1A	F.A.P. RFE. = 330	SECTION = 103R-4	COUNTY = COOK	TOTAL SHEETS = 877	SHEET NO. = 431	
SHT.PLAN	PLOT SCALE = 100.000000' / in.	CHECKED - DAD	REVISED -			SCALE: 1"=50'	SHEET 4 OF 7 SHEETS	STA. 255+00.00 TO STA. 278+00.00	E-20		CONTRACT NO. 60M61
	PLOT DATE = 3/15/2013	DATE = 03/13/2013	REVISED -			ILLINOIS FED. AID PROJECT					
DT60M61-SHT-E20.dgn 3/15/2013 2:27:10 PM											