


NOTES:

- 1. SEE DRAWING E-1 FOR ELECTRICAL SYMBOL LIST AND ABBREVIATIONS. SEE DRAWING E-2 FOR ELECTRICAL GENERAL NOTES.
- 2. CONTRACTOR SHALL REMOVE THE IDENTIFIED TEMPORARY LIGHTING UNITS, TEMPORARY LIGHTING CONTROLLERS, ALL ASSOCIATED UTILITY SERVICE WORK, AND THE TEMPORARY WIRING DURING CONSTRUCTION STAGE 2, ONCE ALL OF THE PROPOSED ROADWAY LIGHTING UNITS ALONG THE EAST SIDE OF LAGRANGE ROAD ARE INSTALLED, ENERGIZED, TESTED, AND APPROVED BY THE ENGINEER.
- 3. CONTRACTOR MUST REINSTALL EXISTING LIGHTING UNIT ON NEW POLE FOUNDATION WITH THE SAME BOLT CIRCLE DIAMETER AS WAS DETERMINED PER NOTE 3 ON DRAWING EL-6. SEE 100T STANDARD DRAWING BE-301 FOR PROPOSED LIGHTING UNIT FOUNDATION DETAILS. FOUNDATION WILL BE PAID FOR UNDER THE "LIGHT POLE FOUNDATION, 24" DIAMETER" PAY ITEM. SEPARATE PAYMENT WILL NOT BE MADE.
- 4. CONTRACTOR MUST CONFIRM THAT A 20A, 120V GFCI RECEPTACLE HAS BEEN INSTALLED AT 15'-0" ABOVE THE BASE OF EXISTING POLE TO BE RELOCATED. RECEPTACLES MUST BE INSTALLED WHERE ABSENT, AND CONNECTED TO RECEPTACLE PANEL WITHIN THE PROPOSED LIGHTING CONTROLLER "C103". SEE IDOT STANDARD BE-400 FOR PROPOSED RECEPTACLE REOUIREMENTS. THE COST OF ALL REOUIRED RECEPTACLE SWILL BE INCLUDED IN THE "LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 12 FT. MAST ARM" PAY ITEM. SEPARATE PAYMENT WILL NOT BE MADE.
- 5. CONTRACTOR MUST CHANGE THE LIGHTING UNIT IDENTIFICATION ON THE REINSTALLED LIGHTING UNIT TO THE NEW NAME SHOWN ON THIS DRAWING.



54								
	FILE NAME =	USER NAME = michal_bartusiewicz	DESIGNED - MAE	REVISED -			F.A.P SECTION	COUNTY TOTAL SHEET
_	D160M61-SHT-E29.dgn		DRAWN - MAE	REVISED -	STATE OF ILLINOIS	151st STREET TEMPORARY ROADWAY LIGHTING PLAN - STAGE 1B	330 103R-4	COOK 877 440
5	!	PLOT SCALE = 100.0000000 '/ in.	CHECKED - DAD	REVISED -	DEPARTMENT OF TRANSPORTATION		E-29	CONTRACT NO. 60M61
	SHT_PLAN	PLOT DATE = 3/15/2013	DATE - 03/13/2013	REVISED -		SCALE: 1"=50" SHEET 6 OF 7 SHEETS STA. 498+50.00 TO STA. 531+50.00	ILLIN	OIS FED. AID PROJECT