


**NOTES:**

1. SEE DRAWING GE-1 FOR ELECTRICAL SYMBOL LIST AND ABBREVIATIONS. SEE DRAWING GE-2 FOR ELECTRICAL GENERAL NOTES.
2. SEE IDOT STANDARD DRAWING BE-400 FOR PROPOSED LIGHTING UNIT DETAILS. SEE IDOT STANDARD DRAWING BE-301 FOR PROPOSED LIGHTING UNIT FOUNDATION DETAILS, UNLESS NOTED OTHERWISE.
3. SEE DRAWING ED-7 FOR PROPOSED RETAINING WALL MOUNTED LIGHTING UNIT INSTALLATION DETAILS.
4. CONTRACTOR SHALL DISCONNECT AND REMOVE TEMPORARY AERIAL SERVICES AND CONNECT THE NEW UNIT DUCT TO PREVIOUSLY INSTALLED UNIT DUCT. CONTRACTOR SHALL EXCAVATE AT LIGHTING UNIT FOUNDATION, PULL THE TEMPORARY WIRING FROM ELBOW, AND INSTALL NEW WIRING IN ELBOW AND SPLICE TO PREVIOUSLY INSTALLED UNIT DUCT IN LIGHTING UNIT HANDHOLE. CHANGE OVER SHALL BE DONE DURING DAYLIGHT HOURS AFTER ALL OTHER WORK IS DONE. MAINTAIN EXISTING LIGHTING DURING HOURS OF DARKNESS.



100 S. WACKER DR.  
 SUITE 500  
 CHICAGO, IL 60606  
 TEL (312) 939-1000  
 FAX (312) 939-4198  
**URS**

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
D160M61-SHT-E32.dgn	michal_bar_tustewicz	MAE	
		DRAWN -	REVISED -
		MAE	
SHT.PLAN	PLOT SCALE =	CHECKED -	REVISED -
	100.000000' / in.	DAD	
	PLOT DATE =	DATE -	REVISED -
	3/15/2013	03/13/2013	

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

<b>US 45 (LaGRANGE ROAD)</b> <b>TEMPORARY ROADWAY LIGHTING PLAN - STAGE 3</b>			
SCALE: 1"=50'	SHEET 2 OF 7 SHEETS	STA. 195+00.00 TO STA. 225+00.00	

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	103R-4	COOK	877	443
<b>E-32</b>			CONTRACT NO.	60M61
<small>ILLINOIS FED. AID PROJECT</small>				