

**EROSION CONTROL SCHEDULE
SHEETS ER-02 TO ER-30**

ITEM	20101000 TEMPORARY FENCE	25100127 MULCH, METHOD 3A	25100630 EROSION CONTROL BLANKET	25100635 HEAVY DUTY EROSION CONTROL BLANKET	25200110 SODDING, SALT TOLERANT	28000200 EARTH EXCAVATION FOR EROSION CONTROL	28000250 TEMPORARY EROSION CONTROL SEEDING	28000305 TEMPORARY DITCH CHECKS	28000400 PERIMETER EROSION BARRIER	28001000 AGGREGATE (EROSION CONTROL)	72000200 SIGN PANEL - TYPE 2	X2800520 ABOVE GRADE INLET FILTERS
	FOOT	ACRE	SO YD	SO YD	SO YD	CU YD	POUND	FOOT	FOOT	TON	SO FT	EACH
SHEET												
ER-02	145	0.00	0	0	0	0	0.00	0	0	0	0	2
ER-03	1340	1.00	105	0	2745	240	106.25	434	700	6	54	29
ER-04	405	1.25	0	0	1228	0	125.00	234	87	0	18	63
ER-05	605	0.75	0	0	0	0	75.00	116	607	0	18	28
ER-06	207	0.75	0	0	0	0	75.00	0	0	0	18	23
ER-07	0	1.00	102	471	0	205	105.50	0	1997	28	0	43
ER-08	337	0.50	100	0	1573	330	35.00	79	1669	29	0	50
ER-09	1770	0.25	98	0	3643	285	25.00	268	31	8	0	21
ER-10	0	0.00	0	0	0	0	0.00	0	0	0	0	10
ER-11	0	0.00	0	0	0	0	0.00	0	0	0	0	16
ER-12	0	0.00	0	0	0	0	0.00	0	0	0	0	17
ER-13	0	0.00	0	0	0	0	0.00	0	0	0	0	9
ER-14	776	0.75	57	391	0	235	87.25	0	379	8	0	27
ER-15	1452	0.50	86	0	4160	255	50.00	470	148	8	0	53
ER-16	2619	0.50	120	0	2858	335	56.75	286	0	6	0	49
ER-17	0	1.00	0	0	873	0	100.00	136	1626	0	0	15
ER-18	0	0.00	0	0	0	0	0.00	0	0	0	0	8
ER-19	0	0.00	0	0	0	0	0.00	0	0	0	0	17
ER-20	0	0.00	0	0	0	0	0.00	0	0	0	0	21
ER-21	0	0.00	0	0	0	0	0.00	0	0	0	0	18
ER-22	0	0.00	0	0	0	0	0.00	92	555	0	0	7
ER-23	0	0.00	0	0	0	0	0.00	96	551	0	0	1
ER-24	0	0.50	0	0	717	0	50.00	42	586	0	0	5
ER-25	0	0.25	0	319	0	0	25.00	48	437	0	0	6
ER-26	0	0.25	0	553	0	0	25.00	0	1158	0	0	10
ER-27	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-28	0	0.25	0	0	0	0	25.00	0	595	0	0	2
ER-29	0	0.00	0	0	0	0	0.00	0	0	0	0	0
ER-30	0	0.00	0	0	0	0	0.00	0	0	0	0	0
SUB TOTAL	9,656	9.50	668	1,734	17,797	1,885	965.75	2,301	11,126	93		550
AT THE ENGINEER'S DISCRETION	966	1.00	67	173	1,780	190	96.25	230	1,113	9		55
GRAND TOTAL	10,622	10.50	735	1,907	19,577	2,075	1,062	2,531	12,239	102	108	605

APEX
CONSULTING ENGINEERS, LLC
111 E. Wacker Drive, Suite 528
Chicago, IL 60601

FILE NAME *	USER NAME * #USER*	DESIGNED - LN	REVISED - Δ 04/12/2013	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	EROSION CONTROL SCHEDULE OF QUANTITIES NORTH CONTRACT				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - HAA	REVISED -						330	103R-5	COOK	778	41
PLDT SCALE * #SCALE#	CHECKED - WHI	REVISED -	REVISED -		SCALE: N.T.S. SHEET NO. 4 OF 5 SHEETS STA. TO STA.				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
PLDT DATE * #DATE#	DATE - 3/15/2013	REVISED -	REVISED -		SC-04				CONTRACT NO. 60M62				