

● 131ST / HIGH SCHOOL ■ MULTI-USE PATH

•• 80% FED, 10% STATE, 10% OP; ••• 80% FED, 13% STATE, 7% PP

OP=VILLAGE OF ORLAND PARK, PP=VILLAGE OF PALOS PARK, STA=STATE

\*=SPECIALTY ITEMS

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 135TH	TRAFFIC SIGNALS SOUTHMOOR	TRAFFIC SIGNALS 131ST	TRAFFIC SIGNALS CREEK	TRAFFIC SIGNALS	INTERCONNECT	NEW SIDEWALK/	ORLAND PARK 100%	NEW SIDEWALK/	PALOS PARK 100%	WATER MAIN/SAN SEWER	SPECIAL BRIDGE/RET WALL
				80% FED 20% STA	100% OP	80% FED 20% STA	100% OP	80% FED 20% STA	•••	80% FED 20% STA	80% FED 20% STA	80% FED 20% OP	100% OP	80% FED 20% PP	100% PP	100% OP	80% FED
				0003	0021	0021	0021	0021	0021	0021	0021	0028	0021	0028	0021	0043	0040
				1 NP MODIL,01	2 OTPOL,01	3 NP MODIL,01	4 OTPOL,02	5 NP MODIL,01	6 MODIL,02	7 MODIL,01	8 MODIL,01	9 NP MODIL,01	10 OTPOL,03	11 NP MODIL,02	12 OTPOL,02	13 OTPOL,01	14 MODIL,01
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	292	292													
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	277	277													
20100500	TREE REMOVAL, ACRES	ACRE	0.50	0.50													
20101000	TEMPORARY FENCE	FOOT	6305	6305													
20101100	TREE TRUNK PROTECTION	EACH	14	14													
20101200	TREE ROOT PRUNING	EACH	3	3													
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	2	2													
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	6	6													
20200100	EARTH EXCAVATION	CU YD	37843	37843													
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	19734	19734													
20400800	FURNISHED EXCAVATION	CU YD	25689	25689													
20600200	GRANULAR EMBANKMENT, SPECIAL	CU YD	416														416
20800150	TRENCH BACKFILL	CU YD	17945	17945													
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SO YD	69140	69140													

URS  
 000 S. WYCKER DR.  
 SUITE 500  
 CHICAGO, IL 60606  
 TEL (312) 939-0000  
 FAX (312) 939-4198

FILE NAME : DIG6M62-SHT-500.dgn	USER NAME : Anthony.Platt	DESIGNED -	REVISED -
SHT_PLAY	PLOT SCALE : 100.0000' / 1"	DRAWN -	REVISED -
	PLOT DATE : 3/19/2013	CHECKED -	REVISED -
		DATE - 03/13/13	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**  
 SCALE: SHEET 1 OF 26 SHEETS STA. TO STA.

F.A.P RTE. 330	SECTION 103R-5	COUNTY COOK	TOTAL SHEETS 778	SHEET NO. 5
CONTRACT NO. 60M62			ILLINOIS FED. AID PROJECT	