

131ST/HIGH SCHOOL MULTI-USE PATH

80% FED, 10% STATE, 10% OP, \*\*\* 80% FED, 13% STATE, 7% PP  
 OP=VILLAGE OF ORLAND PARK, PP=VILLAGE OF PALOS PARK, STA=STATE  
 \*=SPECIALTY ITEMS

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
				ROADWAY 80% FED 20% STA 0003	LIGHTING 100% OP 0021	TRAFFIC SIGNALS 135TH 80% FED 20% STA 0021	TRAFFIC SIGNALS SOUTHMOOR 100% OP 0021	TRAFFIC SIGNALS 131ST 80% FED 20% STA 0021	TRAFFIC SIGNALS CREEK *** 0021	TRAFFIC SIGNALS 131ST/HIGH 80% FED 20% STA 0021	INTERCONNECT 0021	NEW SIDEWALK/ MULTI-USE 80% FED 20% OP 0028	ORLAND PARK 100% 100% OP 0021	NEW SIDEWALK/ MULTI-USE 80% FED 20% PP 0028	PALOS PARK 100% 100% PP 0021	WATER MAIN/SAN SEWER 0043	SPECIAL BRIDGE/RET WALL 80% FED 20% STA 0040	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	161	161														
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	964	964														
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	482	482														
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1734	1734														
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	67	67														
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	689	689														
50102400	CONCRETE REMOVAL	CU YD	412															412
50200100	STRUCTURE EXCAVATION	CU YD	12390	544														11846
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	451															451
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1															1
50300225	CONCRETE STRUCTURES	CU YD	5331.5	50.5														5281.0
50300285	FORM LINER TEXTURED SURFACE	SQ FT	37352															37352
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5500															5500
50500505	STUD SHEAR CONNECTORS	EACH	2263															2263

URS  
 100 S. WABLER DR.  
 SUITE 500  
 CHICAGO, IL 60606  
 TEL (312) 939-0000  
 FAX (312) 939-4988

FILE NAME : 0160MB2-SHT-500.dgn	USER NAME : Anthony.Plutz	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 3/19/2013	DATE - 03/13/13	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
SCALE:	SHEET 6 OF 26 SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 103R-5	COUNTY COOK	TOTAL SHEETS 778	SHEET NO. 10
CONTRACT NO. 60M62			ILLINOIS FED. AID PROJECT	