

80% FED, 10% STATE, 10% OP; *** 80% FED, 13% STATE, 7% PP
 OP=VILLAGE OF ORLAND PARK, PP=VILLAGE OF PALOS PARK, STA=STATE
 *=SPECIALTY ITEMS

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE															
				ROADWAY	LIGHTING	TRAFFIC SIGNALS 135TH	TRAFFIC SIGNALS SOUTHMOOR	TRAFFIC SIGNALS 131ST	TRAFFIC SIGNALS CREEK	TRAFFIC SIGNALS 131ST/HIGH	INTERCONNECT	NEW SIDEWALK/MULTI-USE	ORLAND PARK 100%	NEW SIDEWALK/MULTI-USE	PALOS PARK 100%	WATER MAIN/SAN SEWER	SPECIAL BRIDGE/RET WALL		
				80% FED 20% STA	100% OP	80% FED 20% STA	100% OP	80% FED 20% STA	***	80% FED 20% STA	80% FED 20% STA	80% FED 20% OP	100% OP	80% FED 20% PP	100% PP	100% OP	80% FED 20% STA		
60264130	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1															
60403700	LIDS, TYPE 1, OPEN LID	EACH	20	20															
60403800	LIDS, TYPE 1, CLOSED LID	EACH	40	40															
60404940	FRAMES AND GRATES, TYPE 23	EACH	41	41															
60404950	FRAMES AND GRATES, TYPE 24	EACH	1	1															
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5															
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5															
60500040	REMOVING MANHOLES	EACH	25	25															
60500050	REMOVING CATCH BASINS	EACH	67	67															
60500060	REMOVING INLETS	EACH	39	39															
60500070	REMOVING MANHOLES TO MAINTAIN FLOW	EACH	1	1															
60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	5	5															
60500405	FILLING VALVE VAULTS	EACH	5																5
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	15	15															

100 S. WACKER DR.
 SUITE 500
 CHICAGO, IL 60606
 TEL (312) 939-1000
 FAX (312) 939-4199

URS