

80% FED, 10% STATE, 10% OP, *** 80% FED, 13% STATE, 7% PP
 OP=VILLAGE OF ORLAND PARK, PP=VILLAGE OF PALOS PARK, STA=STATE
 *=SPECIALTY ITEMS

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	LIGHTING	TRAFFIC SIGNALS 135TH	TRAFFIC SIGNALS SOUTHMOOR	TRAFFIC SIGNALS 131ST	TRAFFIC SIGNALS CREEK	TRAFFIC SIGNALS 131ST/HIGH	INTERCONNECT	NEW SIDEWALK/MULTI-USE	ORLAND PARK 100%	NEW SIDEWALK/MULTI-USE	PALOS PARK 100%	WATER MAIN/SAN SEWER	SPECIAL BRIDGE/RET WALL
				80% FED 20% STA	100% OP	80% FED 20% STA	100% OP	80% FED 20% STA	***	80% FED 20% STA	80% FED 20% STA	80% FED 20% OP	100% OP	80% FED 20% PP	100% PP	100% OP	80% FED 20% STA
				0003	0021	0021	0021	0021	0021	0021	0021	0028	0021	0028	0021	0043	0040
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	10	10													
* 72400310	REMOVE SIGN PANEL - TYPE 1	SO FT	262	262													
* 72400320	REMOVE SIGN PANEL - TYPE 2	SO FT	125	125													
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	10	10													
* 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2													
* 72900200	METAL POST - TYPE B	FOOT	790	790													
* 73000100	WOOD SIGN SUPPORT	FOOT	87	87													
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	474	474													
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11336	11336													
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2047	2047													
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	405	405													
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	25	25													
* 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1466	1466													
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	53235	53235													

URS
 100 S. WACKER DR.
 SUITE 500
 CHICAGO, IL 60606
 TEL (312) 339-1000
 FAX (312) 339-4598

FILE NAME : D:\6062-SHT-500.dgn	USER NAME : Anthony.Plutz	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE : 1/8"=1'-0"	CHECKED -	REVISED -
	PLOT DATE : 3/19/2013	DATE - 03/13/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET	16 OF 26 SHEETS	STA. TO STA.

F.A.P RTE. 330	SECTION 103R-5	COUNTY COOK	TOTAL SHEETS 778	SHEET NO. 20
CONTRACT NO. 60M62				ILLINOIS FED. AID PROJECT